



**ENVIRONMENTAL • GEOTECHNICAL  
BUILDING SCIENCES • MATERIALS TESTING**

**RUN-ON AND RUN-OFF CONTROL SYSTEM PLAN  
5 YEAR ASSESSMENT**

TYPE III RESTRICTED WASTE LANDFILL  
A.B. BROWN GENERATING STATION  
8511 WELBORN ROAD  
MOUNT VERNON, INDIANA 47620

ATC PROJECT NO. 170LF01149

OCTOBER 7, 2021

PREPARED FOR:

A.B. BROWN GENERATING STATION  
8511 WELBORN ROAD  
MOUNT VERNON, INDIANA 47620

ATTENTION: MS. ANGELA M. CASBON-SHELLER



October 7, 2021

Ms. Angela M. Casbon-Scheller  
CenterPoint Energy Indiana South, Inc.  
1 N. Main Street  
P.O. Box 209  
Evansville, Indiana 47702-0209

Re: **Run-on and Run-off Controls System Plan  
5 Year Assessment**

Type III Restricted Waste Landfill  
A.B. Brown Generating Station  
Mount Vernon, IN 47620  
ATC Project No. 170LF01149

ATC Group Services LLC

7988 Centerpoint Dr.  
Suite 100  
Indianapolis, IN 46256

Phone +1 317 849 4990  
Fax +1 317 849 4278

[www.atcgroupservices.com](http://www.atcgroupservices.com)

Dear Ms. Casbon-Scheller:

ATC Group Services LLC (ATC) is pleased to present the following Run-On Run-Off Control System (ROROCS) Plan for the A.B. Brown Generating Station Type III Restricted Waste Landfill located at 8511 Welborn Road, Mount Vernon, IN 47620.

As required by 40 CFR 257.81, the owner or operator of a coal combustion residuals (CCR) landfill must design, construct, operate, and maintain:

1. A run-on control system to prevent flow onto the active portion of the CCR unit during the peak discharge from a 24-hour, 25-year storm;
2. A run-off control system from the active portion of the CCR unit to collect and control at least the water volume resulting from a 24-hour, 25-year storm; and
3. The frequency for revising/updating the plan is every five (5) years. Original date of the current ROROCS plan is October 2016.

Contained herein is a summary report which demonstrates that the A.B. Brown Type III Restricted Waste Landfill design measures are compliant with the CCR Rule.


We appreciate the opportunity to assist you with this project. If you have any questions concerning information contained in this letter, please do not hesitate to call any of the undersigned at 317.849.4990.

Sincerely,

**ATC Group Services LLC**

Juan D. Carrizo, P.E.  
Senior Project Engineer

Brent A. Miller, C.H.M.M.  
Principal Scientist



Michael Thornbrue, P.E.  
Senior Project Engineer

---

Prepared for:

SOUTHERN INDIANA GAS AND ELECTRIC COMPANY  
CENTERPOINT ENERGY INDIANA SOUTH, INC.

A.B. BROWN GENERATING STATION  
TYPE III RESTRICTED WASTE LANDFILL

**RUN-ON RUN-OFF  
CONTROL SYSTEMS PLAN  
5 YEAR ASSESSMENT**

A.B. Brown Generating Station  
8511 Welborn Road  
Mount Vernon, Indiana 47620

OCTOBER 7, 2021

Prepared by:



7988 Centerpoint Drive, Suite 100  
Indianapolis, Indiana 46256

---

## Executive Summary

The A.B. Brown Generating Station Type III Restricted Waste Landfill located at 8511 Welborn Road in Mount Vernon, IN 47620, received its initial Solid Waste Land Disposal Facility Permit from Indiana Department of Environmental Management (IDEM) in 1979 and an expansion permit in 1992. The IDEM-approved plans for this facility include a number of erosion control and run-off measures designed to contain stormwater flow from both interim and final cover conditions of the landfill. Additional grading measures and perimeter features prevent run-on flow from entering the site.

The CCR Rule requires that all stormwater drainage structures including channels, culverts, and pipe systems be designed to convey at least the flows from the 25-year, 24-hour storm event. This report documents that the engineering structures for run-off and run-on control have been sized appropriately to meet this condition.

# Table of Contents

<b>1</b>	<b>Introduction .....</b>	<b>1</b>
<b>2</b>	<b>Regulatory Requirements .....</b>	<b>1</b>
2.1	Federal CCR Rule.....	1
2.2	Preamble to the Federal CCR Rule.....	1
<b>3</b>	<b>Design Methodology.....</b>	<b>2</b>
3.1	Design Storm.....	2
3.2	Rainfall Abstractions .....	2
3.3	Run-Off and Routing Methodology.....	2
<b>4</b>	<b>Run-On Control .....</b>	<b>3</b>
4.1	Topography.....	3
4.2	Perimeter Roadway .....	3
<b>5</b>	<b>Run-Off Control.....</b>	<b>3</b>
5.1	Erosion Control Measures.....	3
5.2	Flow Conveyance and Capture Measures .....	3
<b>6</b>	<b>Conclusions.....</b>	<b>3</b>

## Appendices

<b>Appendix A:</b>	<b>Design Storm and Structure Overview</b>
<b>Appendix B:</b>	<b>Calculations for Run-On Control System</b>
Section 1:	Run-On Control System Summary
Section 2:	References
<b>Appendix C:</b>	<b>Calculations for Run-Off Control System</b>
Section 1:	Run-Off Control System Interim Conditions Summary
Section 2:	Run-Off Control System Final Cover Conditions Summary
Section 3:	References
<b>Appendix D:</b>	<b>Surface Water Control and Design Plan Sheets</b>

# 1 Introduction

---

ATC prepared this Run-On and Run-Off Control System (ROROCS) Plan for the A.B. Brown Generating Station Type III Restricted Waste Landfill (Fig. 1) in accordance with 40 CFR 257.81 (run-on and run-off controls for Coal Combustion Residuals landfills). This ROROCS Plan documents that the facility control systems have been designed and constructed to meet the Coal Combustion Residuals (CCR) rule following specified engineering calculations for the 24-hour, 25-year design storm. This ROROCS Plan will be placed in the facility's operating record as required by 40 CFR 257.105(g)(3).

## 2 Regulatory Requirements

---

### 2.1 Federal CCR Rule

As required by 40 CFR 257.81, the owner or operator of a CCR landfill must design, construct, operate, and maintain:

1. A run-on control system to prevent flow onto the active portion of the CCR unit during the peak discharge from a 24-hour, 25-year storm; and
2. A run-off control system from the active portion of the CCR unit to collect and control at least the water volume resulting from a 24-hour, 25-year storm.


Additional requirements of the CCR Rule state that the ROROCS Plan must be updated once every five (5) years and placed with the Operating Record for as long as the landfill continues to be active. The previous update was prepared on October 12, 2016.

The original permit and subsequent minor modification applications reviewed and approved by IDEM include sedimentation and erosion control systems that meet these requirements.

### 2.2 Preamble to the Federal CCR Rule

The preamble to the federal CCR Rule provides additional description regarding the intent of the requirements. Regarding run-off control, the following quotation from the preamble is relevant.

*The owner or operator must design, construct, operate, and maintain the CCR landfill in such a way that any run-off generated from at least a 24-hour, 25-year storm must be collected through hydraulic structures, such as drainage ditches, toe drains, swales, or other means, and controlled so as to not adversely affect the condition of the CCR landfill. EPA has promulgated these requirements to minimize the detention time of run-off on the CCR landfill and minimize infiltration into the CCR landfill, to dissipate storm water run-off velocity, and to minimize erosion of CCR landfill slopes. An additional concern with run-off from CCR landfills is the water quality of the run-off, which may collect suspended solids from the landfill slopes.*



**A.B. BROWN GENERATING STATION  
TYPE III RWS LANDFILL**

8511 WELBORN ROAD  
MOUNT VERNON, INDIANA 47620  
POSEY COUNTY, INDIANA

Project Number:  
17OLF01149

Drawing File:  
SEE LEFT

Date:  
9/21

Scale:  
AS SHOWN

Drn. By:  
BH

Ckd. By:  
MT

App'd By:  
JDC

Figure:  
1



1

The following sections include a description of the run-on and run-off control systems is included in the following sections of this report.

## 3 Design Method

---

### 3.1 Design Storm

The 24-hour, 25-year design storm is the mandatory protection standard for run-on and run-off control systems. The A.B. Brown Landfill was designed to handle run-off flow from this event. The 25-year design storm was derived from the National Oceanic and Atmospheric Administration (NOAA) TP 40 data for Posey County, Indiana. The storm generates 5.4 inches of precipitation for this location. All run-on and run-off control systems were designed for this capacity.

### 3.2 Rainfall Abstractions

Losses in rainfall volume are accounted for in abstractions (losses). The SCS Method was applied to calculate the correct curve number for the land use and soil types of the site. This curve number was then applied to calculate the losses and the actual run-off. SCS equations are below:

$$S = 1000/CN - 10 \quad \text{[Equation 1]}$$

$$I_a = 0.2 * S \quad \text{[Equation 2]}$$

Where:

S = potential maximum retention after run-off begins (in.);

CN = curve number; and

$I_a$  = initial abstraction (in.)

The initial abstraction is a function of the land use conditions as represented by the composite curve number for the tributary drainage area. For example, the initial abstraction for run-off from CCR material having a curve number of 79 is calculated as follows:

$$I_a = 200/79 - 2 = 0.53 \text{ inches}$$

### 3.3 Run-off and Routing Method

The hydrologic/hydraulic models SWMM, SEDCAD 4, and HydroCAD were used to generate the flow velocities and flow depths for each of the run-on / run-off control measures. The SWMM Model (version 5.1), developed by EPA, and the SEDCAD4 Model, developed by Civil Software Design & Warner of the University of Kentucky, emulate the Natural Resources Conservation Services (NRCS) TR55 Model. The SEDCAD4 program was used for designing run-off control measures of the western half of the landfill in the 2007 IDEM Minor Modification Permit Application. The SWMM model was used to assess the run-off controls for the Interim Conditions.



The HydroCAD model was developed by HydroCAD Software Solutions LLC and was used for designing run-off control measures of the eastern half of the landfill in the 2012 IDEM Minor Modification Permit Application.

The routing calculations from these programs used SCS Curve Number method. All erosion control measures were linked to drainage channels and reservoir areas using the modelling programs. The routing flow paths are included with the modelling results in Appendix B and Appendix C.

## 4 Run-On Control

---

### 4.1 Topography

The site of the A.B. Brown Landfill is located north of the Ohio River and west of Bayou Creek. The surrounding area is mostly flat and the landfill is the highest feature in this area. The landfill is protected from run-on flow by Franklin Road to the west, Welborn Road to the east, and also by natural drainage relief around the landfill perimeter as shown in Figure 1.

### 4.2 Perimeter Roadway

The landfill area is bounded by Welborn Road to the east and an access road for the generating station to the south. West Franklin Road is also present approximately 1,000 feet west of the landfill as shown in Figure 1. The roadway embankment heights generally vary between three (3) and five (5) feet above natural grade preventing run-on flow to the landfill area (see Appendix B). Furthermore the minimum road grade sits well above the 100-year backwater elevation of the Ohio River, ensuring insulation of the A.B. Brown Landfill during the Interim and Final Cover conditions.

## 5 Run-Off Control

---

### 5.1 Erosion Control Measures

A series of diversion berms and slope terraces have been constructed on the landfill to direct run-off flow through the conveyance system. These berms prevent disturbance of the CCR materials during the design storm event. All berms typically have 2H:1V to 3H:1V sideslopes with seeding and erosion control mats as needed. The berm height is two (2) feet which adequately protects from the approximately one (1) foot calculated flow depth of the design storm.

### 5.2 Flow Conveyance and Capture Measures

Flow from diversion berms is directed into riprapped downchutes or pipe downdrains which discharge into the perimeter ditch system at various locations. The encircling landfill perimeter ditch system is divided into two (2) reaches beginning at a high ground split point on the south side of the landfill. The first reach flows clockwise from the split until flow reaches the Landfill Settling Basin. The Landfill Settling Basin outlets to the Capital Pond through a gravity-fed barrel culvert. Both the Landfill Settling Basin and Capital Pond direct flow to the NPDES outfall area.

The second ditch reach flows counter-clockwise from the south split wrapping around the eastern and northern perimeters before routing to the Stormwater Surge Basin at the northwest corner of the landfill. The Stormwater Surge Basin, built from a former borrow area, captures water coming from partially closed and covered portions of the landfill. The Stormwater Surge Basin, Capital Pond, and Landfill Settling Basin together have enough storage to contain the 25-year, 24-hour design storm run-off from the entire A.B. Brown Landfill Solid Waste Boundary area during both Interim and Final Cover Conditions.

## 6 Conclusions

---

As required by 40 CFR 257.81, the A.B. Brown Landfill run-on control system is designed to prevent flow onto the active portion of the CCR unit during the peak discharge from a 25-year 24-hour storm, and the A.B. Brown Landfill run-off control system is designed to collect and control the surface water volume resulting from a 25-year 24-hour storm.

## Appendices

### Appendix A: Design Storm and Structure Overview

### Appendix B: Calculations for Run-On Control System

Section 1: Run-On Control System Summary  
Section 2: References


### Appendix C: Calculations for Run-Off Control System

Section 1: Run-Off Control System Interim Conditions Summary  
Section 2: Run-Off Control System Final Cover Conditions Summary  
Section 3: References

### Appendix D: Surface Water Control and Design Plan Sheets

## Appendix A: Design Storm and Structure Overview

# RAINFALL - 25 YEAR FREQUENCY - 24 HOUR DURATION



REFERENCE  
TECHNICAL PAPER NO. 40  
NATIONAL WEATHER SERVICE




STATE OF INDIANA  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF WATER



## FLOW CONTROL STRUCTURE CONVEYANCE TABLE

FLOW CONTROL STRUCTURE	FLOW TYPE CONVEYED
Perimeter Channels	Run-On & Run-Off
Downdrains (Inlet & Pipe)	Run-Off
Erosion Control Berms	Run-Off
Outlets to Retention Pond	Run-On & Run-Off
Retention Ponds	Run-On & Run-Off



**LEGEND:**

- 426 1/23/21 EXISTING TOPOGRAPHIC ELEVATIONS
- PERMITTED SOLID WASTE BOUNDARY
- RUN OFF ZONE
- RUN ON ZONE

Drn. By:	BH
Project Number:	170LF01149
Drawing File:	SEE LOWER LEFT
Ckt. By:	JC
App'd By:	
Ckt. Date:	



**RUN-ON AND RUN-OFF PRODUCING ZONES**  
 A. B. BROWN GENERATING STATION  
 TYPE III RWS LANDFILL  
 8511 WELBORN ROAD  
 MOUNT VERNON, INDIANA 47620

Date:	09/23/2021
Scale:	AS SHOWN
Figure:	A

## Appendix B: Calculations for Run-On Control System

Section 1: Run-On Control System Summary  
Section 2: References



# Appendix B: Calculations for Run-On Control System

Section 1: Run-On Control System Summary

## **OBJECTIVE:**

The objective of this calculation is to demonstrate that the perimeter stormwater controls for the A.B. Brown Type III Restricted Waste Landfill have capacity to control run-on flow from the 24-hour, 25-year storm. According to EPA, run-on is defined as

*“...Any liquid that drains over land onto any part of a CCR landfill or any lateral expansion of a CCR landfill. In surface water hydrology, run-on is a quantity of surface run-off, or excess rain, snowmelt, or other sources of water, which flows from an upstream catchment area onto a specific downstream location.”*

Although perimeter ditches and retention pond systems handle *both* run-on and run-off flow, the hydraulic capacities of these structures will be evaluated under this run-on section since the structures are located in the run-on producing zone of the landfill and adjoining area.

## **METHOD:**

The capacity of the perimeter stormwater controls will be evaluated using the SCS method and Manning's equation. For this design the 25-year design storm [Ref. 4] will be used which exceeds the minimum standards.

## **DEFINITION OF VARIABLES:**

A = area;  
b = bottom width of flow through channel;  
d = flow depth through channel;  
CN = curve number;  
D = channel depth;  
i = rainfall depth;  
n = Manning's roughness coefficient for flow through channel;  
Q = discharge flow;  
S = longitudinal slope of the channel flow;  
T = top width of flow through channel;  
V = velocity of flow through channel; and  
Z = channel side slope.

## **CALCULATIONS:**


### **1.0 Perimeter Road**

Drainage from the encompassing watershed of the landfill flows in the southwest direction. The natural gradient of the watershed is high on the northeast side of the landfill to low on the northwest side of the landfill where flow joins the unnamed tributary to the Ohio River (see USGS Streamstats watershed maps [Ref. 2]).

Run-on flow divides around the landfill as it reaches the perimeter road embankment of Welborn Road at the eastern edge of the solid waste boundary. This road prevents run-on stormwater from reaching the final closure landfill area. The design of the perimeter haul road system allows for insular protection of the landfill because the road grade is 3-5 feet above natural ground which is greater than the depth of overland flow. The embankment of the haul road, in addition to the final cover grade, together act as an effective means to divert run-on flow from the outside subbasin areas.

The 100-year flood backwater elevation of the nearby Ohio River is approximately 373.5' NAVD [Ref. 5]. By comparison the lowest grade of the perimeter road system is 408 feet (Fig. 1). This indicates that in addition to protection from the upstream catchment run-on flow, the final cover area would also be protected from backwater of the Ohio River.

Figure 1 – Perimeter Road Profile



## 2.0 Perimeter Stormwater Channels

Two joining reaches of a perimeter ditch system are located outside the base of the A.B. Brown Type III Restricted Waste Landfill. The first reach of the perimeter ditch begins at the southern end of the landfill and conveys stormwater in a clockwise direction to the lined Landfill Settling Basin at the southwest corner of the landfill.

The second perimeter ditch reach conveys flow in a counterclockwise direction to the northwest corner of the landfill through a former borrow area that was converted to the Stormwater Surge Basin. The Stormwater Surge Basin ranges in depth from five (5) to eight (8) feet and covers an area of approximately five (5) acres.

Design criteria for the perimeter ditch channels were evaluated by first estimating the peak flow to the channels using the SCS method [Ref. 3], and then evaluating the channel capacity using Manning's equation. The channels were designed for capacity of the 24-hour, 25-year storm.

## 2.1 Channel peak flow rates

The landfill perimeter and final cover were both assumed to contribute flow to the channel reaches. The time of concentration for the storm water runoff was calculated as the cumulative sum of upstream contributing berm and drowdrain subwatersheds. Peak flow rates to the channels were estimated using the 2007 SEDCAD4 model [Ref. 1] and are summarized in the following table:

Rainfall			Contribution of Flow from Landfill (Run-Off)			
SEDCAD Channel Reach	Design Storm Event (years)	Rainfall 24-Hour {i} (in.)	Land Use	Curve Number {CN}	Drainage Area {A} (ac.)	Peak Runoff {Q} (cfs)
#12	25	5.4	Vegetated	78	221.2	353.0
#20	25	5.4	Vegetated	78	2.8	8.9
#21	25	5.4	Vegetated	78	18.9	52.2
#22	25	5.4	Vegetated	78	41.5	113.0
#28	25	5.4	Vegetated	78	50	80.6
#29	25	5.4	Vegetated	78	60.3	85.9
#30	25	5.4	Vegetated	78	204.3	342.7
#31	25	5.4	Vegetated	78	64.4	182.0

## 2.2 Channel Capacity

The stormwater perimeter channels consist of trapezoidal channels with dimensions presented in the following table:

SEDCAD ID	Bottom Width {b}	Depth {D}	Left Side Slope {Z <sub>1</sub> H:V}	Right Side Slope {Z <sub>2</sub> H:V}	Top Width {T}	Approximate Longitudinal Slope {S}
	(ft)	(ft)			(ft)	(ft/ft)
#12	12	4	3	3	36	0.007
#20	12	4	3	3	36	0.020
#21	12	4	3	3	36	0.033
#22	12	4	3	3	36	0.019
#28	12	4	3	3	36	0.020
#29	12	4	3	3	36	0.067
#30	12	4	3	3	36	0.007
#31	12	4	3	3	36	0.013

The capacity of both ditches was evaluated using Manning's equations as presented in the following equations:

$$V = 1.49/n R^{2/3} S^{1/2}$$

$$Q = VA$$

The flow cross-section area “A” and wetted perimeter “P” were calculated based on the geometry of a trapezoidal channel with a flow depth “d”, bottom width “b”, left side slope “Z1”, and right side slope “Z2”, using the following relationships:

$$A = b*d + 0.5*Z1*d^2 + 0.5*Z2*d^2$$

$$P = b + \text{sqrt}[(Z1*d)^2 + d^2] + \text{sqrt}[(Z2*d)^2 + d^2]$$

The channel was assumed to have grass lining and flow capacity was evaluated for the design slope condition subject to the 25-year, 24-hour design storm event. Channel capacity calculated for the selected grade and runoff is shown in the following tables:

Table 4: Channel Capacity for Perimeter Ditch Reaches Flowing Clockwise										
SEDCAD	Storm	Channel	Manning's	Flow	Flow	Velocity	Channel	Peak	Channel	Freeboard
ID	Recurrence	Lining	n	Depth	Area		Capacity	Runoff	Capacity	
	Interval								> Peak	
			{n}	{d}	{A}	{V}	{Q}	{Q}	Runoff?	
	(years)			(ft.)	(ft <sup>2</sup> )	(ft/s)	(cfs)	(cfs)		(in.)
#20	25	Grass	0.0680	0.41	5.50	1.6	557.2	8.9	YES	43.1
#21	25	Grass	0.0517	0.70	16.52	3.2	941.4	52.2	YES	39.6
#22	25	Grass	0.0373	0.99	22.66	5.0	990.0	113.0	YES	36.1
#31	25	Grass	0.0340	1.35	34.20	5.3	898.4	182.0	YES	31.8

Table 5: Channel Capacity for Perimeter Ditch Reaches Flowing Counter-Clockwise										
SEDCAD	Storm	Channel	Manning's	Flow	Flow	Velocity	Channel	Peak	Channel	Freeboard
ID	Recurrence	Lining	n	Depth	Area		Capacity	Runoff	Capacity	
	Interval								> Peak	
			{n}	{d}	{A}	{V}	{Q}	{Q}	Runoff?	
	(years)			(ft.)	(ft <sup>2</sup> )	(ft/s)	(cfs)	(cfs)		(in.)
#28	25	Grass	0.0354	1.66	14.36	5.6	1070.3	80.6	YES	28.1
#29	25	Grass	0.0440	1.58	10.62	8.1	1576.0	85.9	YES	29.0
#30	25	Grass	0.0284	2.51	55.16	6.2	789.3	342.7	YES	17.9
#12	25	Grass	0.0270	2.60	51.54	6.9	830.2	353.0	YES	16.8

Modeling results show that the perimeter ditches have enough capacity to meet the design storm with considerable freeboard leftover.

### **3.0 Ponds**

Run-on and run-off flow from the perimeter ditch system is routed to three (3) different basins. The ditch reaches which flow counterclockwise route to the Stormwater Surge Basin at the northwest corner of the landfill. The Stormwater Surge Basin occupies an area of approximately 5 acres in size. The Stormwater Surge Basin handles only non-contact water. This energy dissipating area allows for sedimentation to occur before eventual discharge to an NPDES outfall area.

Ditch reaches which flow clockwise route to the Landfill Settling Basin at the southwest corner of the landfill. According to 2015 construction plans submitted as part of the Storm Water Pollution Prevention Plan (SWP3), the marked (Normal) 'Pool Elevation' is 397.5' leaving 3.5 feet of available storage during typical operating conditions. This storage sedimentation space is used for treatment of contact waters produced from the active cell portions of the landfill. A pipe connecting the Landfill Settling Basin to the Capital Pond has an upstream invert (overflow) elevation of 400.0' allowing for additional storage before treatment occurs at the treatment facility of the generating station.

Combined storage available in the Stormwater Surge Basin, Landfill Settling Basin, and Capital Pond is sufficient to handle the 25-year storm volume from the landfill and adjacent contributing areas.

#### **DISCUSSION:**

The perimeter stormwater controls for the A.B. Brown Type III Restricted Waste Landfill have capacity to control both run-on and non-contact water run-off for the 24-hour, 25-year storm.

#### **REFERENCES:**

1. SEDCAD 4 by Civil Software Design, LLC.
2. StreamStats in Indiana. U.S. Geological Survey. <<http://streamstats.usgs.gov/>>.
3. United States Department of Agriculture, "Urban Hydrology for Small Watersheds", Technical Release 55, June 1986.
4. Hershfield, David M., "Technical Paper No. 40 Rainfall Frequency Atlas of the United States for Durations from 30 Minutes to 24 Hours and Return Periods from 1 to 100 Years", NOAA National Weather Service, obtained January 14, 2005.
5. Indiana Floodplain Information Portal (INFIP). <<http://dnrmaps.dnr.in.gov/appsphp/fdms/>>.

## Appendix B: Calculations for Run-On Control System

### Section 2: References

<b>REFERENCE NO.</b>	<b>DESCRIPTION</b>
1	SEDCAD 4
2	USGS Streamstats – Drainage Areas
3	USDA TR-55
4	NOAA Technical Paper No. 40
5	INFIP Report


Reference 1: SEDCAD 4

[See Appendix C – Section 3, Reference 1 for Combined Run-On and Run-Off Modeling Results]



Reference 2: USGS Streamstats – Drainage Areas

# StreamStats Version 3.0 : Indiana



Reference 3: USDA TR-55



**United States  
Department of  
Agriculture**

Natural  
Resources  
Conservation  
Service

Conservation  
Engineering  
Division

Technical  
Release 55

June 1986

# Urban Hydrology for Small Watersheds

## TR-55

### SCS runoff curve number method

The SCS Runoff Curve Number (CN) method is described in detail in NEH-4 (SCS 1985). The SCS runoff equation is

$$Q = \frac{(P - I_a)^2}{(P - I_a) + S} \quad [\text{eq. 2-1}]$$

where

- Q = runoff (in)
- P = rainfall (in)
- S = potential maximum retention after runoff begins (in) and
- I<sub>a</sub> = initial abstraction (in)

Initial abstraction (I<sub>a</sub>) is all losses before runoff begins. It includes water retained in surface depressions, water intercepted by vegetation, evaporation, and infiltration. I<sub>a</sub> is highly variable but generally is correlated with soil and cover parameters. Through studies of many small agricultural watersheds, I<sub>a</sub> was found to be approximated by the following empirical equation:

$$I_a = 0.2S \quad [\text{eq. 2-2}]$$

By removing I<sub>a</sub> as an independent parameter, this approximation allows use of a combination of S and P to produce a unique runoff amount. Substituting equation 2-2 into equation 2-1 gives:

$$Q = \frac{(P - 0.2S)^2}{(P + 0.8S)} \quad [\text{eq. 2-3}]$$

S is related to the soil and cover conditions of the watershed through the CN. CN has a range of 0 to 100, and S is related to CN by:

$$S = \frac{1000}{\text{CN}} - 10 \quad [\text{eq. 2-4}]$$

Figure 2-1 and table 2-1 solve equations 2-3 and 2-4 for a range of CN's and rainfall.

### Factors considered in determining runoff curve numbers

The major factors that determine CN are the hydrologic soil group (HSG), cover type, treatment, hydrologic condition, and antecedent runoff condition (ARC). Another factor considered is whether impervious areas outlet directly to the drainage system (connected) or whether the flow spreads over pervious areas before entering the drainage system (unconnected). Figure 2-2 is provided to aid in selecting the appropriate figure or table for determining curve numbers.

CN's in table 2-2 (*a* to *d*) represent average antecedent runoff condition for urban, cultivated agricultural, other agricultural, and arid and semiarid rangeland uses. Table 2-2 assumes impervious areas are directly connected. The following sections explain how to determine CN's and how to modify them for urban conditions.

### Hydrologic soil groups

Infiltration rates of soils vary widely and are affected by subsurface permeability as well as surface intake rates. Soils are classified into four HSG's (A, B, C, and D) according to their minimum infiltration rate, which is obtained for bare soil after prolonged wetting. Appendix A defines the four groups and provides a list of most of the soils in the United States and their group classification. The soils in the area of interest may be identified from a soil survey report, which can be obtained from local SCS offices or soil and water conservation district offices.

Most urban areas are only partially covered by impervious surfaces: the soil remains an important factor in runoff estimates. Urbanization has a greater effect on runoff in watersheds with soils having high infiltration rates (sands and gravels) than in watersheds predominantly of silts and clays, which generally have low infiltration rates.

Any disturbance of a soil profile can significantly change its infiltration characteristics. With urbanization, native soil profiles may be mixed or removed or fill material from other areas may be introduced. Therefore, a method based on soil texture is given in appendix A for determining the HSG classification for disturbed soils.

Manning's equation is:

$$V = \frac{1.49r^{\frac{2}{3}}s^{\frac{1}{2}}}{n} \quad [\text{eq. 3-4}]$$

where:

- V = average velocity (ft/s)
- r = hydraulic radius (ft) and is equal to  $a/p_w$
- a = cross sectional flow area (ft<sup>2</sup>)
- $p_w$  = wetted perimeter (ft)
- s = slope of the hydraulic grade line (channel slope, ft/ft)
- n = Manning's roughness coefficient for open channel flow.

Manning's n values for open channel flow can be obtained from standard textbooks such as Chow (1959) or Linsley et al. (1982). After average velocity is computed using equation 3-4,  $T_t$  for the channel segment can be estimated using equation 3-1.

### Reservoirs or lakes

Sometimes it is necessary to estimate the velocity of flow through a reservoir or lake at the outlet of a watershed. This travel time is normally very small and can be assumed as zero.

### Limitations

- Manning's kinematic solution should not be used for sheet flow longer than 300 feet. Equation 3-3 was developed for use with the four standard rainfall intensity-duration relationships.
- In watersheds with storm sewers, carefully identify the appropriate hydraulic flow path to estimate  $T_c$ . Storm sewers generally handle only a small portion of a large event. The rest of the peak flow travels by streets, lawns, and so on, to the outlet. Consult a standard hydraulics textbook to determine average velocity in pipes for either pressure or nonpressure flow.
- The minimum  $T_c$  used in TR-55 is 0.1 hour.


- A culvert or bridge can act as a reservoir outlet if there is significant storage behind it. The procedures in TR-55 can be used to determine the peak flow upstream of the culvert. Detailed storage routing procedures should be used to determine the outflow through the culvert.

### Example 3-1

The sketch below shows a watershed in Dyer County, northwestern Tennessee. The problem is to compute  $T_c$  at the outlet of the watershed (point D). The 2-year 24-hour rainfall depth is 3.6 inches. All three types of flow occur from the hydraulically most distant point (A) to the point of interest (D). To compute  $T_c$ , first determine  $T_t$  for each segment from the following information:

Segment AB: Sheet flow; dense grass; slope ( $s$ ) = 0.01 ft/ft; and length ( $L$ ) = 100 ft. Segment BC: Shallow concentrated flow; unpaved;  $s$  = 0.01 ft/ft; and  $L$  = 1,400 ft. Segment CD: Channel flow; Manning's  $n$  = .05; flow area ( $a$ ) = 27 ft<sup>2</sup>; wetted perimeter ( $p_w$ ) = 28.2 ft;  $s$  = 0.005 ft/ft; and  $L$  = 7,300 ft.

See figure 3-2 for the computations made on worksheet 3.



**Table 7-4** Classification of vegetation cover as to degree of retardance

Retardance	Cover	Condition
A	Weeping lovegrass	Excellent stand, tall (average 30 in)
	Reed canarygrass or Yellow bluestem ischaemum	Excellent stand, tall (average 36 in)
B	Smooth bromegrass	Good stand, mowed (average 12 to 15 in)
	Bermudagrass	Good stand, tall (average 12 in)
	Native grass mixture (little bluestem, blue grama, and other long and short midwest grasses)	Good stand, unmowed
	Tall fescue	Good stand, unmowed (average 18 in)
	Sericea lespedeza	Good stand, not woody, tall (average 19 in)
	Grass-legume mixture—Timothy, smooth bromegrass, or orchardgrass	Good stand, uncut (average 20 in)
	Reed canarygrass	Good stand, uncut (average 12 to 15 in)
	Tall fescue, with birdsfoot trefoil or ladino clover Blue grama	Good stand, uncut (average 18 in) Good stand, uncut (average 13 in)
C	Bahiagrass	Good stand, uncut (6 to 8 in)
	Bermudagrass	Good stand, mowed (average 6 in)
	Redtop	Good stand, headed (15 to 20 in)
	Grass-legume mixture—summer (orchardgrass, redtop, Italian ryegrass, and common lespedeza)	Good stand, uncut (6 to 8 in)
	Centipedegrass	Very dense cover (average 6 in)
	Kentucky bluegrass	Good stand, headed (6 to 12 in)
D	Bermudagrass	Good stand, cut to 2.5-in height
	Red fescue	Good stand, headed (12 to 18 in)
	Buffalograss	Good stand, uncut (3 to 6 in)
	Grass-legume mixture—fall, spring (orchardgrass, redtop, Italian ryegrass, and common lespedeza)	Good stand, uncut (4 to 5 in)
	Sericea lespedeza or Kentucky bluegrass	Good stand, cut to 2-in height. Very good stand before cutting
E	Bermudagrass	Good stand, cut to 1.5-in height
	Bermudagrass	Burned stubble


**Table 7-5** Retardance curve index by retardance class

SCS retardance class	Retardance curve index $C_I$
A	10.0
B	7.64
C	5.60
D	4.44
E	2.88

Reference 4: NOAA Technical Paper No. 40



# RAINFALL - 25 YEAR FREQUENCY - 24 HOUR DURATION



REFERENCE  
TECHNICAL PAPER NO. 40  
NATIONAL WEATHER SERVICE



STATE OF INDIANA  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF WATER



Reference 5: Indiana Floodplain Information Portal  
(INFIP) Report



# Indiana Floodplain Information Portal Report

## Point of Interest

**Effective Flood Zone:**

X

**Preliminary Flood Zone:**

N/A

**Best Available Flood Zone:**

X

**Approximate Flood Elevation:**

373.5ft NAVD88



**Source:**

Zone AE Profile Conversion








**Nearest Stream:**

OHIO RIVER

## Map Legend

-  Point of Interest
-  Nearest Point on Stream

## Effective Flood Zone

-  0.2% Annual Chance Flood Hazard
-  1% Annual Chance Flood Hazard - Zone A (Approximate Study)
-  1% Annual Chance Flood Hazard - Zone AE (Detailed Study)
-  1% Annual Chance Flood Hazard - Floodway
-  1% Annual Chance Flood Hazard - Zone AH
-  1% Annual Chance Flood Hazard - Zone AO
-  Zone X - Protected by Levee

## Site Map with Effective Flood Zone



Approximate scale 1:36,000

## Disclaimer

This data is a digital representation of the former paper Flood Insurance Rate Maps (FIRMs) for counties that have completed the Map Modernization Initiative. The data on counties derived from the official FEMA digital products (DFIRM) represent official FEMA designations of the Special Flood Hazard Areas. This data can be used for official National Flood Insurance Program (NFIP) purposes in accordance with the FEMA Mitigation Directorate Policy document titled "Use of Digital Flood Hazard Data" dated November 29, 2007. For the non-modernized counties, the Effective is enhanced by the addition of the floodplain data from digitized paper copies of the FIRMs and the information should be considered advisory only. For these non-modernized counties, the paper maps are the official FEMA documents for regulatory and insurance purposes. Once the NFHL is official, the Effective is updated with the newly published information. For the status of counties published by FEMA please see <http://www.floodmaps.fema.gov/NFHL/status.shtml>.

## Appendix C: Calculations for Run-Off Control System

Section 1:	Run-Off Control System Interim Conditions Summary
Section 2:	Run-Off Control System Final Cover Conditions Summary
Section 3:	References

# Appendix C: Calculations for Run-Off Control System

Section 1: Run-Off Control System Interim Conditions Summary

## **OBJECTIVE:**

The objective of this calculation is to evaluate the temporary run-off control measures for the active cells at the A.B. Brown Landfill and to assess its capacity to control contact water run-off for the 25-year, 24-hour storm during interim conditions. The temporary run-off control measures for interim (active) phase cells include a temporary collection sump system (North and South Sumps), a perimeter ditch system, the Landfill Settling Basin, and the Capital Pond.

## **METHOD:**

The required sizing of run-off control measures was evaluated using the Soil Conservation Service (SCS) Curve Number method for calculating runoff. The EPA's SWMM model was used to carry out the hydrologic/hydraulic (H/H) analysis of the drainage system.

## **DEFINITION OF VARIABLES:**

A = area;  
CN = curve number;  
Q = flow;

## **CALCULATIONS:**

### **1.0 Contact water run-off for interim conditions**

Prior to closure of the landfill and installation of final cover run-off control measures, operations of interim cell areas utilize interim run-off control measures. In many cases the interim run-off control measures overlap or are the same as those used during final cover conditions but since the active area (interim cells) and final cover area (entire landfill) differ in size, grading, and configuration, different routing procedures are followed for control of stormwater.

The Eastern Landfill Area, which is closed and inactive, already has installed the final cover berms, downdrains, and perimeter ditch segments which will operate during both interim and final cover conditions. The Western Landfill Area, northern half, is also closed with run-off controls (terrace berms and riprap downchutes) already installed. Development of the Western Landfill Area, southern and eastern portions is considered the Interim (active) Area. The approximate drainage areas are depicted in the Surface Water Control Plan which is included in Attachment 1. Conveyance of the surface water run-off from these areas to the Landfill Settling Basin and Capital Pond via a temporary holding sump is described below.

#### *1.1 Estimate run-off volume for interim conditions*

A H/H analysis of the interim site conditions was conducted using the SWMM model for the 25-year storm event. The tributary drainage area is CCR material, which is assumed to as a hydric soil class B with a Curve Number of 79 based on engineering experience. The SCS Curve Number method calculates the runoff from each interim cell during the 25-year, 24-hour storm event and these results were used to size the runoff control measures. The results of the SWMM model analysis are summarized as shown in the tables included below.

Interim Cell ID	Storm Recurrence Interval (years)	Rainfall for 25-year 24-Hour Storm (in.)	Curve Number (CN)	Drainage Area (ac.)	25-Year 24-hr Run-Off Volume per Cell (ac-ft)
17 North	25	5.4	79	2.52	0.74
17 South	25	5.4	79	3.26	0.89
18 North	25	5.4	79	4.08	1.20
18 South	25	5.4	79	6.90	0.98
TOTAL INTERIM CELL RUNOFF VOLUME					3.81

### 1.2 Describe typical runoff control measures

Sizing of all interim runoff control measures was done for the 25-year storm, 24-hour. Cells 17 and 18 North and South are graded to flow west to two (2) temporary collection sumps, identified as North and South Sumps, and these are connected via an equalizer pipe. The drainage collected in the sumps is then routed to the Landfill Settling Basin.

The storage volume of the two (2) sumps was estimated based on the topographic survey conducted on 1/23/2021 for the landfill site and these been accounted in the SWMM model. The depths of the north and south sumps are 12 and 11 feet respectively. The storage area provided by the two (2) sumps are listed in Table 2 for the North Sump and Table 3 for the South Sump.

Contour Elevation ft	Contour Area Sq. Ft	Description
413	2,117	Bottom elevation of Sump
414	2,866	
415	3,664	
417	5,030	
418	8,435	
419	9,994	
420	11,508	
421	13,178	
422	14,485	
423	15,891	
424	16,866	
425	16,884	Top elevation of Sump

Contour Elevation ft	Contour Area Sq. Ft	Description
414	101	Bottom elevation of Sump
415	1,968	
416	4,691	
417	6,668	
418	9,212	
419	11,042	
420	13,431	
421	15,878	
422	18,293	
423	20,353	
424	24,547	
425	25,095	Top elevation of Sump

### 1.3 Evaluate hydraulic performance of control measures

The results of the SWMM model are included in Attachment 2. Based on the H/H model results the storage sumps, North and South sumps provide the necessary storage capacity to contain the 25-year 24-hour storm runoff volume from the interim cells. Therefore the sump system is adequately sized to handle the runoff from the design storm.

Hydrologic Node ID	Average Depth (ft.)	Maximum Depth (ft.)	Maximum Hydraulic Grade (ft)	Maximum Total Inflow (cfs)	Storage Capacity > Runoff Volume?
North_Sump	5.97	10.97	423.97	24.26	YES
South_Sump	5.36	9.97	423.97	28.25	YES

The results of the SWMM model demonstrate that the surface water runoff volume from the active cells are contained within the sump system as designed.

### **DISCUSSION:**

The interim storage sump system for the A.B. Brown Landfill active cells has the capacity to control the runoff from the 25-year, 24-hour storm.




**ATTACHMENTS:**

1. Surface Water Control Plan, Active Cells, Restricted Waste Landfill.
2. Hydrologic/Hydraulic SWMM Model Results, 25-year 24-hour Storm Event, Active Cells.

**ATTACHMENT 1**


**Surface Water Control Plan,  
Active Cells,  
Restricted Waste Landfill**



**LEGEND:**

- 426 — 1/23/21 EXISTING TOPOGRAPHIC ELEVATIONS
- - - PERMITTED SOLID WASTE BOUNDARY
- - - APPROXIMATE LIMITS OF WASTE
- - - DRAINAGE BASIN BOUNDARY
- - - EXISTING PIPE
- APPROXIMATE LIMITS OF PARTIAL CLOSURE AREA  
SOIL FINAL COVER
- APPROXIMATE LIMITS OF PARTIAL CLOSURE AREA  
COMPOSITE FINAL COVER
- VERTICAL EXPANSION DISPOSAL AREA
- ACTIVE DISPOSAL AREA
- FUTURE DEVELOPMENT OF A CCR LANDFILL

MANHOLE



Project Number: 1701021149  
 Drawing File Location: 9/21  
 Date: 9/21  
 AS SHOWN  
 App'd By: JC  
 Checked By: BH

Company Name:  
 ATC GROUP SERVICES, LLC  
 7688 CENTERPOINT DR.  
 SUITE 100  
 INDIANAPOLIS, IN 46256  
 PHONE +1 317 849 4900  
 FAX +1 317 849 4278  
 WWW.ATCGROUPSERVICES.COM

**ATC**

Drawing Title:  
 SURFACE WATER CONTROL PLAN FOR ACTIVE CELLS  
 TYPE III RMS LANDFILL  
 8511 WELBORN ROAD  
 MOUNT VERNON, INDIANA 47620

Sheet:  
 1

**ATTACHMENT 2**

**Hydrologic/Hydraulic SWMM Model Results,  
25-year 24-hour Storm Event,  
Active Cells.**

# Hydrologic/Hydraulic SWMM Model Results, 25-year 24-hour Storm Event, Active Cells

EPA STORM WATER MANAGEMENT MODEL - VERSION 5.1 (Build 5.1.014)

\*\*\*\*\*  
 NOTE: The summary statistics displayed in this report are based on results found at every computational time step, not just on results from each reporting time step.  
 \*\*\*\*\*

\*\*\*\*\*  
 Analysis Options

\*\*\*\*\*  
 Flow Units ..... CFS  
 Process Models:  
   Rainfall/Runoff ..... YES  
   RDII ..... NO  
   Snowmelt ..... NO  
   Groundwater ..... NO  
   Flow Routing ..... YES  
   Ponding Allowed ..... NO  
   Water Quality ..... NO  
 Infiltration Method ..... CURVE\_NUMBER  
 Flow Routing Method ..... DYNWAVE  
 Surcharge Method ..... EXTRAN  
 Starting Date ..... 09/23/2021 00:00:00  
 Ending Date ..... 09/24/2021 06:00:00  
 Antecedent Dry Days ..... 0.0  
 Report Time Step ..... 00:15:00  
 Wet Time Step ..... 00:05:00  
 Dry Time Step ..... 01:00:00  
 Routing Time Step ..... 30.00 sec  
 Variable Time Step ..... YES  
 Maximum Trials ..... 8  
 Number of Threads ..... 1  
 Head Tolerance ..... 0.005000 ft

*****	Volume	Depth
Runoff Quantity Continuity	acre-feet	inches
*****	-----	-----
Total Precipitation .....	7.542	5.400
Evaporation Loss .....	0.000	0.000
Infiltration Loss .....	2.541	1.819
Surface Runoff .....	4.862	3.481
Final Storage .....	0.143	0.102
Continuity Error (%) .....	-0.057	

*****	Volume	Volume
Flow Routing Continuity	acre-feet	10^6 gal
*****	-----	-----
Dry Weather Inflow .....	0.000	0.000
Wet Weather Inflow .....	4.875	1.588
Groundwater Inflow .....	0.000	0.000

```

RDII Inflow ..... 0.000 0.000
External Inflow ..... 0.000 0.000
External Outflow ..... 0.000 0.000
Flooding Loss ..... 0.000 0.000
Evaporation Loss ..... 0.000 0.000
Exfiltration Loss ..... 0.000 0.000
Initial Stored Volume .... 0.000 0.000
Final Stored Volume ..... 4.861 1.584
Continuity Error (%) ..... 0.281

```

```

*****
Time-Step Critical Elements
*****
Link Equalize_pipe (15.33%)

```

```

*****
Highest Flow Instability Indexes
*****
All links are stable.

```

```

*****
Routing Time Step Summary
*****
Minimum Time Step      : 2.21 sec
Average Time Step      : 27.49 sec
Maximum Time Step      : 30.00 sec
Percent in Steady State : 0.00
Average Iterations per Step : 2.00
Percent Not Converging  : 0.00

```

```

*****
Subcatchment Runoff Summary
*****

```

Subcatchment	Total Precip in	Total Runon in	Total Evap in	Total Infil in	Imperv Runoff in	Perv Runoff in	Total Runoff in	Total Runoff 10^6 gal	Peak Runoff CFS	Runoff Coeff
Cell_17_North	5.40	0.00	0.00	1.82	0.00	3.51	3.51	0.24	11.34	0.650
Cell_17_South	5.40	0.00	0.00	1.82	0.00	3.51	3.51	0.31	13.64	0.649
Cell_18_North	5.40	0.00	0.00	1.82	0.00	3.49	3.49	0.39	13.16	0.645
Cell_18_South	5.40	0.00	0.00	1.82	0.00	3.46	3.46	0.65	14.65	0.640

```

*****
Node Depth Summary
*****

```

Node	Type	Average Depth Feet	Maximum Depth Feet	Maximum HGL Feet	Time of Max Occurrence days hr:min	Reported Max Depth Feet
Outfall-1	OUTFALL	0.00	0.00	410.00	0 00:00	0.00

North_Sump	STORAGE	5.97	10.97	423.97	1	06:00	10.97
South_sump	STORAGE	5.36	9.97	423.97	1	06:00	9.97

\*\*\*\*\*  
Node Inflow Summary  
\*\*\*\*\*

Node	Type	Maximum Lateral Inflow CFS	Maximum Total Inflow CFS	Time of Max Occurrence days hr:min	Lateral Inflow Volume 10^6 gal	Total Inflow Volume 10^6 gal	Flow Balance Error Percent
Outfall-1	OUTFALL	0.00	0.00	0 00:00	0	0	0.000 gal
North_Sump	STORAGE	23.90	24.26	0 12:06	0.628	0.752	0.482
South_sump	STORAGE	28.25	28.25	0 12:06	0.96	0.973	0.330

\*\*\*\*\*  
Node Surcharge Summary  
\*\*\*\*\*

No nodes were surcharged.

\*\*\*\*\*  
Node Flooding Summary  
\*\*\*\*\*

No nodes were flooded.

\*\*\*\*\*  
Storage Volume Summary  
\*\*\*\*\*

Storage Unit	Average Volume 1000 ft3	Avg Pcnt Full	Evap Pcnt Loss	Exfil Pcnt Loss	Maximum Volume 1000 ft3	Max Pcnt Full	Time of Max Occurrence days hr:min	Maximum Outflow CFS
North_Sump	48.815	29	0	0	98.353	59	1 06:00	1.77
South_sump	54.232	14	0	0	113.080	29	1 06:00	2.25

\*\*\*\*\*  
Outfall Loading Summary  
\*\*\*\*\*

Outfall Node	Flow Freq Pcnt	Avg Flow CFS	Max Flow CFS	Total Volume 10^6 gal
Outfall-1	0.00	0.00	0.00	0.000
System	0.00	0.00	0.00	0.000

\*\*\*\*\*  
 Link Flow Summary  
 \*\*\*\*\*

Link	Type	Maximum  Flow  CFS	Time of Max Occurrence days hr:min	Maximum  Veloc  ft/sec	Max/ Full Flow	Max/ Full Depth
Equalize_pipe	CONDUIT	2.25	0 11:07	3.62	0.08	1.00
W-south	WEIR	0.00	0 00:00			0.00

\*\*\*\*\*  
 Flow Classification Summary  
 \*\*\*\*\*

Conduit	Adjusted /Actual Length	Fraction of Time in Flow Class								
		Up Dry	Down Dry	Sub Dry	Sup Crit	Up Crit	Down Crit	Norm Ltd	Inlet Ctrl	
Equalize_pipe	1.00	0.29	0.00	0.00	0.66	0.01	0.00	0.04	0.03	0.00

\*\*\*\*\*  
 Conduit Surcharge Summary  
 \*\*\*\*\*

Conduit	Hours Full			Hours Above Full	Hours Capacity
	Both Ends	Upstream	Dnstream	Normal Flow	Limited
Equalize_pipe	18.10	18.10	18.42	0.01	0.01

Analysis begun on: Fri Sep 24 10:15:09 2021  
 Analysis ended on: Fri Sep 24 10:15:09 2021  
 Total elapsed time: < 1 sec



# Appendix C: Calculations for Run-Off Control System

Section 2: Run-Off Control System Final Cover Conditions Summary

## **OBJECTIVE:**

The objective of this calculation is to evaluate the size of run-off control measures within the A.B. Brown Type III Restricted Waste Landfill to provide capacity to control non-contact water run-off for the 24-Hour, 25-Year storm during final cover conditions.

## **METHOD:**

Diversion berm, downdrain, perimeter ditch, and retention pond designs were evaluated using SEDCAD4 and HydroCAD modeling softwares and the Soil Conservation Service (SCS) method for calculating runoff.

## **DEFINITION OF VARIABLES:**

A = area;  
CN = curve number;  
Q = flow;  
T<sub>c</sub> = time of concentration

## **CALCULATIONS**

### **1.0 Contact water run-off for final cover conditions**

After placement of the CCR to achieve a consistent grade across the landfill footprint, the landfill closure area will be covered in protective soil and a vegetative layer. The Western Landfill Area will be graded to drain towards several levels of terrace berms which will outlet to downdrain riprap channels and perimeter ditches. The Eastern Landfill Area will drain into tack-on berms and downdrain pipes which will also outlet to the perimeter ditch system. Run-off from the final cover landfill area will be captured by these design features and conveyed to the west Landfill Settling Basin and northwest Stormwater Surge Basin.

SEDCAD4 and HydroCAD computer softwares [Ref. 1, 2] were used to model the hydraulic performance of the berms, downdrains, perimeter ditches, and ponds for the 24-Hour, 25-Year storm event [Ref. 4].

#### *1.1 Estimate flow to a typical diversion berm*

Two types of diversion berms exist as part of the final cover design of the West Landfill Area. The first type of berm is a side-slope terrace channel berm which conveys run-off flow generated by the steeper (25%) side slopes of the final cover. The second type of berm is a top-of-slope diversion berm which conveys run-off flow generated by the longer, flatter (2.5%) side slope of the final cover running south.

The drainage area to any individual side-slope terrace berm and top-of-slope diversion berm in the West Landfill Area during final cover conditions will be limited to approximately 2.3 acres and 18 acres, respectively. The tributary drainage area is CCR material, which was assumed to be consistent with a hydric soil class B based on engineering experience. Time of concentration was calculated using TR-55 Methodology [Ref. 3]. Below are the SEDCAD4 calculated runoff amounts from both the side-slope terrace diversion berm and top-of-slope diversion berm assuming the maximum drainage area.

Design Feature	SEDCAD Model ID	Storm Frequency	Drainage Area (ac.)	Curve Number	Time of Concentration (hr)	Peak Discharge (cfs)
West End Side-Slope (Terrace) Berm	#10	25yr, 24hr	2.3	78	0.194	6.8
West End Top-of-Slope Berm	#12	25yr, 24hr	18	78	0.339	49

For the East Landfill Area, the HydroCAD calculated run-off amount for the tack-on diversion berm with the greatest drainage area is shown below:

Design Feature	HydroCAD Model ID	Storm Frequency	Drainage Area (ac.)	Curve Number	Time of Concentration (hr)	Peak Discharge (cfs)
East End Tack-On Diversion Berm	West Portion of NW D.A. 2R	25yr, 24hr	6.4	78	0.338	21.3

## 1.2 Describe typical berm and downdrain outlet

### West Landfill Area

On the West Landfill Area the terrace diversion berms are 2 feet high with a 5H:1V side slope on the contact (intercept) face of the berm. The width of each terrace is approximately 10 feet. Terrace berm channels are graded at a 2% slope and route towards riprap channel downdrain structures which feed into the north and south reaches of the perimeter ditch.

The top-of-slope diversion berms on the West Landfill Area are also 2 feet high with 2% channel slopes. These berms have a 4H:1V side slope on both faces of the berm mound.

An average of five (5) terrace berm levels outlet flow to a typical receiving downdrain channel. Downdrain outlets that discharge to the perimeter ditch service (receive flow from) an average of ten (10) terrace runoff areas. There are a total of five (5) downdrain outlets to the perimeter ditch system along the western half of the landfill. The largest drainage area received by any one of these downdrain channels is approximately 23 acres.

### East Landfill Area

The East Landfill Area is designed during final cover conditions to convey flow through a series of tack-on diversion berms and 18"-diameter downdrain pipes. The tack-on berms typically have 3H:1V side slopes with 2% channel slope and the berm height varies from 2 feet (minimum) to 4 feet (maximum) at the end nearest to the downdrain. The increased height of the berm at the downstream end allows for a small temporary ponding buffer zone to form should the downdrains become backed up due to exceedance of design capacity during severe storm events.

### 1.3 Evaluate hydraulic performance of a typical diversion berm

#### West Landfill Area

Based on the stated assumptions, runoff from the 25-Year storm event produces a flow depth of approximately 1.4 feet in the terrace channel. The planned terrace diversion berm height of 2 feet is capable of conveying the storm flow without the berm overtopping.

Design Feature	SEDCAD Model ID	Storm Frequency	Flow Area Design (sq. ft.)	Flow Area Available (sq. ft.)	Flow Depth Design Flow (ft.)	Depth Channel (ft.)	Freeboard (ft.)
West End Side-Slope (Terrace) Berm	#10	25yr, 24hr	8.8	20	1.40	2	0.60

Based on the stated assumptions, runoff from the 25-Year storm event produces a flow depth of approximately 1.7 feet in the top-of-slope diversion berm channel. The planned top-of-slope diversion berm height of 2 feet is capable of conveying the storm flow without the berm overtopping.

Design Feature	SEDCAD Model ID	Storm Frequency	Flow Area Design (sq. ft.)	Flow Area Available (sq. ft.)	Flow Depth Design Flow (ft.)	Depth Channel (ft.)	Freeboard (ft.)
West End Top-of-Slope Berm	#12	25yr, 24hr	35.7	48	1.70	2	0.30

#### East Landfill Area

Based on the stated assumptions, runoff from the 25-Year storm event produces a maximum flow depth of approximately 0.76 feet in the tack-on diversion berm channel. The modeled channel depth is produced based on the maximum drainage area received by a typical berm on the East Landfill Area. The planned diversion berm height of 2-4 feet is capable of conveying the storm flow without the berm overtopping.

Design Feature	HydroCAD Model ID	Storm Frequency	Flow Area Design (sq. ft.)	Flow Area Available (sq. ft.)	Flow Depth Design Flow (ft.)	Depth Channel (ft.)	Freeboard (ft.)
East End Tack-On Diversion Berm	West Portion of NW D.A. 2R	25yr, 24hr	13.2	184	0.76	2	1.24

1.4 Evaluate hydraulic performance of a typical downdrain

West Landfill Area

The downdrain structures for the A.B. Brown West Landfill Area, final cover design are rippapped stormwater channels. The downdrain channels run downhill at the same grade as the landfill. The downdrain channel design has a 2-foot bottom with 1.5-foot depth and 4H:1V side slopes. The downdrain channels use Type I Riprap. Capacity calculations for a typical riprap downdrain are shown below:

Table 5A: Structure Capacity for Riprap Open Channel Downdrains							
SEDCAD ID	Design Storm Event (years)	Channel Bottom (ft.)	Channel Area (ft2)	Velocity (fps)	Design Discharge (cfs)	Flow Capacity (cfs)	Flow Capacity > Design Flow?
#25	25yr, 24hr	2.0	12	10.0	63.8	86.2	YES

East Landfill Area

The downdrain structures for the A.B. Brown East Landfill Area, final cover design are 18"-diameter corrugated polyethylene pipes. Discharges from the subbasins of the East Landfill Area, routed through the downdrains, are calculated below:

Table 5B: Structure Capacity for Pipe Downdrains							
HydroCAD ID	Design Storm Event (years)	Pipe Diameter (ft.)	Pipe Area (ft2)	Velocity (fps)	Design Discharge (cfs)	Flow Capacity (cfs)	Flow Capacity > Design Discharge?
NW – 2R	25yr, 24hr	1.3	1.33	23.6	16.0	31.1	YES
NE – 2R	25yr, 24hr	1.3	1.33	23.2	14.8	31.1	YES
SE – 2R	25yr, 24hr	1.3	1.33	23.2	15.0	31.1	YES
SW – 2R	25yr, 24hr	1.3	1.33	23.5	15.8	31.1	YES

**DISCUSSION:**

Run-off control measures for the A.B. Brown Type III Restricted Waste Landfill have capacity to control non-contact water run-off for the 24-Hour, 25-Year storm during final cover conditions.

**REFERENCES:**

1. SEDCAD4 by Civil Software Design LLC.
2. HydroCAD by HydroCAD Software Solutions LLC.
3. United States Department of Agriculture, "Urban Hydrology for Small Watersheds", Technical Release 55, June 1986.
4. Hershfield, David M., "Technical Paper No. 40 Rainfall Frequency Atlas of the United States for Durations from 30 Minutes to 24 Hours and Return Periods from 1 to 100 Years", NOAA National Weather Service, obtained January 14, 2005.

## Appendix C: Calculations for Run-Off Control System

### Section 3: References

<b>REFERENCE NO.</b>	<b>DESCRIPTION</b>
1	SEDCAD 4 Modeling Results
2	HydroCAD Modeling Results
3	USDA TR-55
4	NOAA Technical Paper No. 40

Reference 1: SEDCAD 4 - Modeling Results



---

## ATC ASSOCIATES, INC.

PROJECT A.B. Brown Landfill Minor Modification

PROJECT NO. \_\_\_\_\_

Storm Water Runoff Calculations

PAGE 1 OF 6

MADE BY DS

DATE 2/07

CHECKED BY \_\_\_\_\_

DATE \_\_\_\_\_

---

### STORM WATER RUNOFF CALCULATIONS

The erosion and stormwater control structures described in this section have been designed, as required, to limit soil erosion to less than 5 tons-per-acre-per-year and adequately convey the 25-year/24-hour storm event (5.43", IDNR 1994, attached). It is our understanding that the existing sedimentation basins are adequate. Soil erosion estimates are attached in a separate calculations section.

**Stormwater flows from seven sub-drainage areas routed through perimeter channels and road-crossing culverts** (see attached figure) were determined for the proposed modification area (NW, NE, SE, S, SW, and W), the completed landfill (E), and an undeveloped area (N) using the SEDCAD4 computer model developed by R.C. Warner of the University of Kentucky and P.J. Schwab of Civil Soft Design. These sub-drainage area flows are based on drainage area, elevation change across the drainage area, flow path length, and soil cover characteristics. These flows were input into the SEDCAD model at their respective locations along the north and south perimeter channels. The model then routed these flows through the north and south perimeter channels which then joined at a location near the southwest corner of the existing retention basin. Because the peak flows from the various sub-drainage areas occur at different times, the model accounts for the timing of these peaks and adjusts the peaks of combined flows accordingly. An output from the model of this drainage system is attached and shows that:

The south perimeter channel conveys 25-year/24-hour stormwater flows from the

SE area (3 acres at 9 cfs peak) which flows west through the South perimeter channel at 9 cfs peak and 1.7 fps to an 18-inch-diameter culvert which flows to the

S area (16 acres at 46 cfs peak) which joins the SE area and flows west through the South perimeter channel at 52 cfs peak and 3.2 fps to the

SW area (23 ac. at 64 cfs peak) which joins the SE and S areas and flows through the South perimeter channel at 113 cfs peak and 5.0 fps to the

W area (23 acres at 72 cfs peak) joins SE, S, and SW areas and flows through a 60-inch-diameter culvert with a 72-inch-dia.drop-inlet and flows west through the

---

## ATC ASSOCIATES, INC.

---

PROJECT A.B. Brown Landfill Minor Modification

PROJECT NO. \_\_\_\_\_

Storm Water Runoff Calculations

PAGE 2 OF 6

---

MADE BY DS

DATE

2/07

CHECKED BY \_\_\_\_\_

DATE \_\_\_\_\_

---

South perimeter channel at 172 cfs peak at 5.2 fps to join the North perimeter channel and flow west through the Combined north/south channel at 411 cfs peak and 5.9 fps.

The north perimeter channel conveys 25-year/24-hour stormwater flows from the

E area (50 acres at 81 cfs peak) which flows through the North perimeter channel at 81 cfs peak and 5.6 fps to the

NE area (10 acres at 31 cfs peak) which joins the E area and flows west through the North perimeter channel at 86 cfs peak and 8.1 fps to the

N area (144 acres at 264 cfs) which joins the E and NE areas to flow west through the North perimeter channel at 343 cfs peak and 6.2 fps to the

NW area (17 ac. at 48 cfs) which joins the E, NE, and N areas and flows through the North perimeter channel with a 353 cfs peak and 6.8 fps to join the South perimeter channel and flow west through the Combined north/south channel at 411 cfs peak and 5.9 fps.

The perimeter channels that transport flows at velocities greater than 5 fps typically require more erosion protection than normal vegetation can provide. Sheet 6 shows a riprap channel downstream from the NE sub-drainage area and turf-reinforcement mats downstream from the N sub-drainage area.

**Maximum design flows within stormwater conveyance structures of a**

- Side-slope terrace channel with a site-maximum area of 2.3 acres, a
- Top-of-slope diversion berm with a site-maximum area of 18 acres, and a
- Riprap-lined downdrain channel with a site-maximum area of 23 acres.

were individually determined by the SEDCAD4 computer model and were found to adequately convey their portions of the 25-year/24-hour storm. Outputs from these models are attached and described below.

**Side-slope terrace channels** lie between 90-ft lengths of 4H:1V, grass-covered, final cover slopes. The 90-ft terrace spacings are based on erosion control calculations

---

# ATC ASSOCIATES, INC.

PROJECT **A.B. Brown Landfill Minor Modification**

PROJECT NO. \_\_\_\_\_

**Storm Water Runoff Calculations**

PAGE **3** OF **6**

---

MADE BY **DS**

DATE

**2/07**

CHECKED BY \_\_\_\_\_

DATE \_\_\_\_\_

---

provided in the "Final Cover Soil Loss Estimates" section of this minor permit modification application. The terrace channels have 2% slopes, are v-shaped with 4H:1V and 5H:1V sideslopes, and are up to 1,000 ft in length. These channels are drained into riprap-lined downdrain channels at the northeast, northwest, west, and the south sides of the proposed final cover modifications.

The attached SEDCAD4 output shows that at the maximum length of 1,000 feet and a maximum area of 2.3 acres, this proposed channel adequately handles the 25-year/24-hour storm flow of 7 cfs.

**Top-of-final-cover diversion berms** have been placed at selected locations on the 5%-sloped top of the final cover. These channels have 2% to 2.7% slopes, are v-shaped with 4H:1V and 20H:1V sideslopes, are up to 1,100 ft in length, and collect runoff from up to 18 acres of 5%-sloped final cover. These channels are drained into riprap-lined downdrain channels at the northeast, northwest, west, and south sides of the proposed final cover modifications.

The attached SEDCAD4 output shows that at the maximum area of 18 acres, this proposed berm adequately diverts the 25-year/24-hour storm flow of 49 cfs.

**Riprap-lined downdrain channels** have 2-ft bottoms, 4H:1V sideslopes, are generally sloped at 25% grades, and flow into the north and south perimeter channels. At the terraces, the riprap is extended an additional 6 feet past the top of the 3H:1V sideslopes.

The attached SEDCAD4 output shows that at the maximum area of 23 acres, the proposed downdrain adequately handles the 25-year/24-hour storm flow of 73 cfs. This model also shows the design features for a riprap-lined plunge pool for dissipation of flow energy. A detail of this plunge pool is shown on Sheet 6 of the engineering drawings.

---

**ATC ASSOCIATES, INC.**

PROJECT **A.B. Brown Landfill Minor Modification**

PROJECT NO. \_\_\_\_\_

**Storm Water Runoff Calculations**

PAGE **4** OF **6**

---

MADE BY **DS**

DATE **1/07**

CHECKED BY \_\_\_\_\_


DATE \_\_\_\_\_

---

Documentation

5/6

# RAINFALL - 25 YEAR FREQUENCY - 24 HOUR DURATION




REFERENCE  
 TECHNICAL PAPER NO. 40  
 NATIONAL WEATHER SERVICE

STATE OF INDIANA  
 DEPARTMENT OF NATURAL RESOURCES  
 DIVISION OF WATER

APRIL 1919.

DATE

PITCH SYMBOL KEY



Symbol	Pitch
[Symbol]	1:1
[Symbol]	1:2
[Symbol]	1:4
[Symbol]	1:8
[Symbol]	1:16
[Symbol]	1:32
[Symbol]	1:64
[Symbol]	1:128
[Symbol]	1:256
[Symbol]	1:512
[Symbol]	1:1024
[Symbol]	1:2048
[Symbol]	1:4096
[Symbol]	1:8192
[Symbol]	1:16384
[Symbol]	1:32768
[Symbol]	1:65536
[Symbol]	1:131072
[Symbol]	1:262144
[Symbol]	1:524288
[Symbol]	1:1048576
[Symbol]	1:2097152
[Symbol]	1:4194304
[Symbol]	1:8388608
[Symbol]	1:16777216
[Symbol]	1:33554432
[Symbol]	1:67108864
[Symbol]	1:134217728
[Symbol]	1:268435456
[Symbol]	1:536870912
[Symbol]	1:1073741824
[Symbol]	1:2147483648
[Symbol]	1:4294967296
[Symbol]	1:8589934592
[Symbol]	1:17179869184
[Symbol]	1:34359738368
[Symbol]	1:68719476736
[Symbol]	1:137438953472
[Symbol]	1:274877906944
[Symbol]	1:549755813888
[Symbol]	1:1099511627776
[Symbol]	1:2199023255552
[Symbol]	1:4398046511104
[Symbol]	1:8796093022208
[Symbol]	1:17592186044416
[Symbol]	1:35184372088832
[Symbol]	1:70368744177664
[Symbol]	1:140737488355328
[Symbol]	1:281474976710656
[Symbol]	1:562949953421312
[Symbol]	1:1125899906842624
[Symbol]	1:2251799813685248
[Symbol]	1:4503599627370496
[Symbol]	1:9007199254740992
[Symbol]	1:18014398509481984
[Symbol]	1:36028797018963968
[Symbol]	1:72057594037927936
[Symbol]	1:144115188075855872
[Symbol]	1:288230376151711744
[Symbol]	1:576460752303423488
[Symbol]	1:1152921504606846976
[Symbol]	1:2305843009213693952
[Symbol]	1:4611686018427387904
[Symbol]	1:9223372036854775808
[Symbol]	1:18446744073709551616
[Symbol]	1:36893488147419103232
[Symbol]	1:73786976294838206464
[Symbol]	1:147573952589676412928
[Symbol]	1:295147905179352825856
[Symbol]	1:590295810358705651712
[Symbol]	1:1180591620717411303424
[Symbol]	1:2361183241434822606848
[Symbol]	1:4722366482869645213696
[Symbol]	1:9444732965739290427392
[Symbol]	1:18889465931478580854784
[Symbol]	1:37778931862957161709568
[Symbol]	1:75557863725914323419136
[Symbol]	1:151115727451828646838272
[Symbol]	1:302231454903657293676544
[Symbol]	1:604462909807314587353088
[Symbol]	1:1208925819614629174706176
[Symbol]	1:2417851639229258349412352
[Symbol]	1:4835703278458516698824704
[Symbol]	1:9671406556917033397649408
[Symbol]	1:19342813113834066795298816
[Symbol]	1:38685626227668133590597632
[Symbol]	1:77371252455336267181195264
[Symbol]	1:154742504910672534362390512
[Symbol]	1:309485009821345068724781024
[Symbol]	1:618970019642690137449562048
[Symbol]	1:1237940039285380274899124096
[Symbol]	1:2475880078570760549798248192
[Symbol]	1:4951760157141521099596496384
[Symbol]	1:9903520314283042199192992768
[Symbol]	1:19807040628566084398385925536
[Symbol]	1:39614081257132168796771851072
[Symbol]	1:79228162514264337593543702144
[Symbol]	1:158456325028528675187087404288
[Symbol]	1:316912650057057350374174808576
[Symbol]	1:633825300114114700748349617152
[Symbol]	1:1267650600228229401496698234304
[Symbol]	1:2535301200456458802993396468608
[Symbol]	1:5070602400912917605986792937216
[Symbol]	1:10141204801825835211973585874432
[Symbol]	1:20282409603651670423947171748864
[Symbol]	1:40564819207303340847894343497728
[Symbol]	1:81129638414606681695788686995456
[Symbol]	1:162259276292133363391573373990912
[Symbol]	1:324518552584266726783146747981824
[Symbol]	1:649037105168533453566293495963648
[Symbol]	1:129807421033706790713258691927296
[Symbol]	1:259614842067413581426517383854592
[Symbol]	1:519229684134827162853034767709184
[Symbol]	1:1038459368697654325706069535418368
[Symbol]	1:2076918737395308651412139070836736
[Symbol]	1:4153837474790617302824278141673472
[Symbol]	1:8307674949581234605648556283346944
[Symbol]	1:16615349899162473211297112566733888
[Symbol]	1:33230699798324946422594225133467776
[Symbol]	1:66461399596649892845188450266935552
[Symbol]	1:13292279919329978569037690053871104
[Symbol]	1:26584559838659957138075380107742208
[Symbol]	1:53169119677319914276150760215484416
[Symbol]	1:106338239354639828552301520430968832
[Symbol]	1:212676478709279657104603040861937664
[Symbol]	1:425352957418559314209206081723875328
[Symbol]	1:850705914837118628418412163447750656
[Symbol]	1:1701411829674237256836824326895501312
[Symbol]	1:3402823659348474513673648653791002624
[Symbol]	1:6805647318696949027347297307582005248
[Symbol]	1:13611294637393898054694594615164010496
[Symbol]	1:27222589274787796109389189230328020992
[Symbol]	1:54445178549575592218778378460656041984
[Symbol]	1:108890357099151184437556756921312083968
[Symbol]	1:217780714198302368875113513842624167936
[Symbol]	1:435561428396604737750227027685248335872
[Symbol]	1:871122856793209475500454055370496671744
[Symbol]	1:174224571378641895100090811074099334368
[Symbol]	1:348449142757283790200181622148198668736
[Symbol]	1:696898285514567580400363244296397337472
[Symbol]	1:1393796571029135160800726488592794674944
[Symbol]	1:2787593142058270321601452977185589349888
[Symbol]	1:5575186284116540643202905954371178699776
[Symbol]	1:11150372568233081286405811908742357399552
[Symbol]	1:22300745136466162572811623817484714799104
[Symbol]	1:44601490272932325145623247634969429592208
[Symbol]	1:89202980545864650291246495269938859184416
[Symbol]	1:178405961091729300582492990539777718368832
[Symbol]	1:356811922183458601164985981079555436737664
[Symbol]	1:713623844366917202329971962159110873475328
[Symbol]	1:1427247687533834404659943924302217746950656
[Symbol]	1:2854495375067668809319887848604435493901312
[Symbol]	1:5708990750135337618639775697208870987802624
[Symbol]	1:11417981500270675237279553994417741975605248
[Symbol]	1:22835963000541350474559107988835483951210496
[Symbol]	1:45671926001082700949118215977670967902420992
[Symbol]	1:91343852002165401898236431955341935804841984
[Symbol]	1:182687704004328803796472863910683871609683968
[Symbol]	1:365375408008657607592945727821367743219367936
[Symbol]	1:730750816017315215185891455642735486438735872
[Symbol]	1:1461501632034630430371782911285470972877471744
[Symbol]	1:292300326406926086074356582257094194575494368
[Symbol]	1:584600652813852172148713164514188389150988736
[Symbol]	1:1169201305627704344297426329028376778301977472
[Symbol]	1:233840261125540868859485265805675355660395488
[Symbol]	1:467680522251081737718970531611350711320790976
[Symbol]	1:935361044502163475437941063222701422641581952
[Symbol]	1:1870722089004326950875882126445402845283163904
[Symbol]	1:3741444178008653901751764252890805690566327808
[Symbol]	1:7482888356017307803503528505781611381132655616
[Symbol]	1:1496577671203461560700705701156322276226531232
[Symbol]	1:2993155342406923121401411402312644552453062464
[Symbol]	1:5986310684813846242802822804625289104906124928
[Symbol]	1:1197262136962769248560564560925057820981249952
[Symbol]	1:2394524273925538497121129121850115641962499904
[Symbol]	1:4789048547851076994242258243700231283924999808
[Symbol]	1:9578097095702153988484516487400462567849999616
[Symbol]	1:1915619419140430797696903297480092513569999232
[Symbol]	1:3831238838280861595393806594960185027139998464
[Symbol]	1:7662477676561723190787613189920370054279996928
[Symbol]	1:1532495535312344638157522637984074010855993856
[Symbol]	1:3064991070624689276315045275968148021711987712
[Symbol]	1:6129982141249378552630090551936296043423975424
[Symbol]	1:12259964282498757105260181103872580086847950848
[Symbol]	1:24519928564997514210520362207745160173695901696
[Symbol]	1:49039857129995028421040724415490320347391803392
[Symbol]	1:98079714259990056842081448830980640694783606784
[Symbol]	1:196159428599980113684162897661961203895567213568
[Symbol]	1:392318857199960227368325795323922407791134427136
[Symbol]	1:784637714399920454736651590647844815582268854272
[Symbol]	1:1569275428799840909473303181295689631164537708544
[Symbol]	1:3138550857599681818946606362591379262329075417088
[Symbol]	1:6277101715199363637893212725182758524658150834176
[Symbol]	1:12554203430398727275786425450365517049316316682304
[Symbol]	1:25108406860797454551572850900731034098632633364608
[Symbol]	1:50216813721594909103145701801462068197265266729216
[Symbol]	1:100433627443189818206291403602924136394530533458432
[Symbol]	1:200867254886379636412582807205848272789061066916864
[Symbol]	1:401734509772759272825165614411696545578122133833728
[Symbol]	1:803469019545518545650331228823393091156244267667456
[Symbol]	1:1606938039091037091300662457646786182312488535334912
[Symbol]	1:3213876078182074182601324915293572364624977070669824
[Symbol]	1:6427752156364148365202649830587144729249954141339648
[Symbol]	1:1285550431272829673040529966117428945849990828267936
[Symbol]	1:2571100862545659346081059932234857891699981656535872
[Symbol]	1:5142201725091318692162119864469715783399963313071744
[Symbol]	1:1028440345018263738432423972893943156679992662614368
[Symbol]	1:2056880690036527476864847945787886313359985325228736
[Symbol]	1:4113761380073054953729695891575772626719970650457472
[Symbol]	1:8227522760146109907459391783151545253439941300914944
[Symbol]	1:16455045520292219814918783566303090506879826001829888
[Symbol]	1:32910091040584439629837567132606181013759652003659776
[Symbol]	1:65820182081168879259675134265212362027519304007319552
[Symbol]	1:131640364162337758519350268530424724055038608014639104
[Symbol]	1:263280728324675517038700537060849448110077216029278208
[Symbol]	1:526561456649351034077401074121698896220154432058556416
[Symbol]	1:1053122913298702068154802142243977924440308640117112832
[Symbol]	1:2106245826597404136309604284487955848880617280234225664
[Symbol]	1:4212491653194808272619208568975911697761234560468451328
[Symbol]	1:8424983306389616545238417137951823395522469120936902656
[Symbol]	1:16849966626779233090478234275903646791044938241873805312
[Symbol]	1:33699933253558466180956468551807293582089876483747610624
[Symbol]	1:67399866507116932361912937103614587164179752967495221248
[Symbol]	1:13479973301423386483982587420723117428835905934990444496
[Symbol]	1:26959946602846772967965174841446234857671811869980888992
[Symbol]	1:53919893205693545935930349682892469715343623739961777984
[Symbol]	1:107839786411387091871860693651789394230687247479923555968
[Symbol]	1:215679572822774183743721387303578788461374494959847111936
[Symbol]	1:431359145645548367487442774607157576922748989919694223872
[Symbol]	1:862718291291096734974885549214315153845497979839388447744
[Symbol]	1:1725436582582193469949771098428630307690995999678776895488
[Symbol]	1:3450873165164386939899542196857260615381991999357553790976
[Symbol]	1:6901746330328773879799084393714521230763983998715107581952
[Symbol]	1:13803492660657547759591768775429042601527967997430215163904
[Symbol]	1:27606985321315095519183537550858085203055935994860430327808
[Symbol]	1:55213970642630191038367075101716170406111871989720860655616
[Symbol]	1:110427941285260382076734150203432340812223743979441721311232
[Symbol]	1:220855882570520764153468300406864681624447487958883442622464
[Symbol]	1:441711765141041528306936600813729363248894975917766885244928
[Symbol]	1:883423530282083056613873201627458726497789951835533774489856
[Symbol]	1:17668470

**Runoff Flows from the**  
**NW, N, NE, E, SE, S, SW, and W**  
**Sub-Drainage Areas**

**AB Brown Type III Landfill**  
**January 2007 Minor Modification**

*Using a 25-year/24-hour design storm, this site's sub-drainage areas NW, N, NE and E have been routed through the north perimeter channel while the W, SW, S, and SE drainage areas have been routed through the south perimeter channel which includes a road-crossing culvert upstream of the S drainage area outlet and a road-crossing culvert downstream of the W drainage area outlet. These north and south perimeter channels meet near the west side of the existing retaining pond and then drain west to the site's existing sedimentation pond.*

## ***General Information***

### ***Storm Information:***

Storm Type:	NRCS Type II
Design Storm:	25 yr - 24 hr
Rainfall Depth:	5.430 inches






















### **Structure Networking:**

Type	Stru #	(flows into)	Stru #	Musk. K (hrs)	Musk. X	Description
Null	#10	==>	#12	0.000	0.000	NW drainage area
Channel	#12	==>	#14	0.056	0.406	North perimeter channel from NE drainage area to junction with south perimeter channel drains NW, N, NE, and N drainage areas
Pond	#13	==>	#31	0.000	0.000	Headwater of 60-inch diameter culvert that drains the south perimeter channel under the perimeter road
Channel	#14	==>	End	0.000	0.000	Channel at southwest corner of existing retention pond that drains the north perimeter and south perimeter channels
Channel	#15	==>	#30	0.000	0.000	N drainage area
Null	#16	==>	#25	0.000	0.000	SW drainage area
Null	#17	==>	#21	0.000	0.000	S drainage area
Null	#18	==>	#20	0.000	0.000	SE drainage area
Channel	#20	==>	#26	0.000	0.000	South perimeter channel from SE to S drainage areas - drains SE area
Channel	#21	==>	#22	0.000	0.000	South perimeter channel from S to SW drainages areas - drains SE and S areas
Channel	#22	==>	#13	0.000	0.000	South perimeter channel from SW drainage area to the 60-inch diameter culvert - drains SW, S, and SE areas
Null	#23	==>	#29	0.000	0.000	NE drainage area
Null	#24	==>	#28	0.000	0.000	E drainage area
Channel	#25	==>	#22	0.000	0.000	SW drainage area - riprap downdrain for the SW drainage area
Culvert	#26	==>	#21	0.000	0.000	South perimeter channel culvert under road between drainage areas SE and S
Null	#27	==>	#13	0.000	0.000	W drainage area
Channel	#28	==>	#29	0.098	0.357	North perimeter channel - existing perimeter channel from E drainage area to NE drainage area - drains E area
Channel	#29	==>	#30	0.010	0.410	North perimeter channel - existing perimeter channel from NE drainage area and N drainage area - drains NE and E areas
Channel	#30	==>	#12	0.022	0.406	North perimeter channel - widened existing perimeter channel from N drainage area to NE drainage area - drains N, NE, and E areas

# SEDCAD 4 for Windows

Copyright 1998 Pamela J. Schwab

Type	Stru #	(flows into)	Stru #	Musk. K (hrs)	Musk. X	Description
Channel	#31	==>	#14	0.008	0.430	South perimeter channels from the 60-inch diameter culvert to the junction between the north and south perimeter channels

		#27 Null				
				#16 Null		
			#25 Chan'l			
					#18 Null	
					#20 Chan'l	
				#26 Culvert		
				#17 Null		
				#21 Chan'l		
			#22 Chan'l			
		#13 Pond				
		#31 Chan'l				
					#24 Null	
				#28 Chan'l		
				#23 Null		
				#29 Chan'l		
				#15 Chan'l		
		#30 Chan'l				
		#10 Null				
		#12 Chan'l				

#14  
Chan'l

**Structure Routing Details:**

Stru #	Land Flow Condition	Slope (%)	Vert. Dist. (ft)	Horiz. Dist. (ft)	Velocity (fps)	Time (hrs)
#12	9. Small streams flowing bankfull	0.67	10.00	1,500.00	7.34	0.056
<b>#12</b>	<b>Muskingum K:</b>					<b>0.056</b>
#16	8. Large gullies, diversions, and low flowing streams	0.00	0.00	0.00	0.00	0.000
<b>#16</b>	<b>Muskingum K:</b>					<b>0.000</b>
#28	8. Large gullies, diversions, and low flowing streams	2.00	30.00	1,500.00	4.24	0.098
<b>#28</b>	<b>Muskingum K:</b>					<b>0.098</b>
#29	8. Large gullies, diversions, and low flowing streams	6.67	20.00	300.00	7.74	0.010
<b>#29</b>	<b>Muskingum K:</b>					<b>0.010</b>
#30	9. Small streams flowing bankfull	0.67	4.00	600.06	7.34	0.022
<b>#30</b>	<b>Muskingum K:</b>					<b>0.022</b>
#31	9. Small streams flowing bankfull	1.33	4.00	300.00	10.39	0.008
<b>#31</b>	<b>Muskingum K:</b>					<b>0.008</b>

***Structure Summary:***

	Immediate Contributing Area (ac)	Total Contributing Area (ac)	Peak Discharge (cfs)	Total Runoff Volume (ac-ft)
#27	22.900	22.900	72.35	5.88
#16	22.600	22.600	63.78	5.80
#25	0.000	22.600	63.78	5.80
#18	2.800	2.800	8.85	0.72
#20	0.000	2.800	8.85	0.72
#26	0.000	2.800	8.85	0.72
#17	16.100	16.100	45.59	4.13
#21	0.000	18.900	52.22	4.85
#22	0.000	41.500	112.98	10.65
#13	In Out	0.000	64.400	185.33
			182.03	16.53
#31	0.000	64.400	182.03	16.53
#24	50.000	50.000	80.57	12.83
#28	0.000	50.000	80.57	12.83
#23	10.300	10.300	30.90	2.64
#29	0.000	60.300	85.92	15.48
#15	144.000	144.000	263.85	36.96
#30	0.000	204.300	342.72	52.44
#10	16.900	16.900	47.64	4.34
#12	0.000	221.200	353.02	56.78
#14	0.000	285.600	411.02	73.31

***Structure Detail:***

Structure #27 (Null)

*W drainage area*

Structure #16 (Null)

*SW drainage area*

Structure #25 (Riprap Channel)

*SW drainage area - riprap downdrain for the SW drainage area*

Trapezoidal Riprap Channel Inputs:

Material: Riprap

Bottom Width (ft)}	Left Sideslope Ratio	Right Sideslope Ratio	Slope (%)	Freeboard Depth (ft)	Freeboard % of Depth	Freeboard Mult. x (VxD)
2.00	3.0:1	3.0:1	25.0	0.50		

Riprap Channel Results:

**PADER Method - Steep Slope Design**

	w/o Freeboard	w/ Freeboard
Design Discharge:	63.78 cfs	
Depth:	1.16 ft	1.66 ft
Top Width:	8.99 ft	11.99 ft
Velocity:	9.96 fps	
X-Section Area:	6.40 sq ft	
Hydraulic Radius:	0.683	
Froude Number:	2.08	
Manning's n:	0.0580	
Dmin:	5.00 in	
D50:	9.00 in	
Dmax:	12.00 in	

Structure #18 (Null)

*SE drainage area*

Structure #20 (Vegetated Channel)

*South perimeter channel from SE to S drainage areas - drains SE area*

Trapezoidal Vegetated Channel Inputs:

Material: Grass mixture

Bottom Width (ft)	Left Sideslope Ratio	Right Sideslope Ratio	Slope (%)	Retardance Classes	Freeboard Depth (ft)	Freeboard % of Depth	Freeboard Mult. x (VxD)	Limiting Velocity (fps)
12.00	3.0:1	3.0:1	2.0	D, B				5.0

Vegetated Channel Results:

	Stability Class D w/o Freeboard	Stability Class D w/ Freeboard	Capacity Class B w/o Freeboard	Capacity Class B w/ Freeboard
Design Discharge:	8.85 cfs		8.85 cfs	
Depth:	0.41 ft		0.81 ft	
Top Width:	14.49 ft		16.84 ft	
Velocity:	1.61 fps		0.76 fps	
X-Section Area:	5.50 sq ft		11.62 sq ft	
Hydraulic Radius:	0.376		0.680	
Froude Number:	0.46		0.16	
Roughness Coefficient:	0.0680		0.2138	

Structure #26 (Culvert)

*South perimeter channel culvert under road between drainage areas SE and S*

Culvert Inputs:

Length (ft)	Slope (%)	Manning's n	Max. Headwater (ft)	Tailwater (ft)	Entrance Loss Coef. (Ke)
130.00	2.30	0.0240	2.20	1.00	0.90

Culvert Results:

Design Discharge = 8.85 cfs

Minimum pipe diameter: 1 - 18 inch pipe(s) required

Structure #17 (Null)

*S drainage area*

Structure #21 (Vegetated Channel)

*South perimeter channel from S to SW drainages areas - drains SE and S areas*

Trapezoidal Vegetated Channel Inputs:

Material: Grass mixture

Bottom Width (ft)	Left Sideslope Ratio	Right Sideslope Ratio	Slope (%)	Retardance Classes	Freeboard Depth (ft)	Freeboard % of Depth	Freeboard Mult. x (VxD)	Limiting Velocity (fps)
12.00	3.0:1	30.0:1	3.3	D, B	0.50			5.0

### Vegetated Channel Results:

	Stability Class D w/o Freeboard	Stability Class D w/ Freeboard	Capacity Class B w/o Freeboard	Capacity Class B w/ Freeboard
Design Discharge:	52.22 cfs		52.22 cfs	
Depth:	0.70 ft	1.20 ft	1.15 ft	1.65 ft
Top Width:	35.13 ft	51.63 ft	50.05 ft	66.55 ft
Velocity:	3.16 fps		1.46 fps	
X-Section Area:	16.52 sq ft		35.77 sq ft	
Hydraulic Radius:	0.470		0.714	
Froude Number:	0.81		0.30	
Roughness Coefficient:	0.0517		0.1480	

### Structure #22 (Vegetated Channel)

*South perimeter channel from SW drainage area to the 60-inch diameter culvert - drains SW, S, and SE areas*

### Trapezoidal Vegetated Channel Inputs:

#### Material: Grass mixture

Bottom Width (ft)	Left Sideslope Ratio	Right Sideslope Ratio	Slope (%)	Retardance Classes	Freeboard Depth (ft)	Freeboard % of Depth	Freeboard Mult. x (VxD)	Limiting Velocity (fps)
20.00	3.0:1	3.0:1	1.9	D, B				5.0

### Vegetated Channel Results:

	Stability Class D w/o Freeboard	Stability Class D w/ Freeboard	Capacity Class B w/o Freeboard	Capacity Class B w/ Freeboard
Design Discharge:	112.98 cfs		112.98 cfs	
Depth:	0.99 ft		1.47 ft	
Top Width:	25.92 ft		28.80 ft	
Velocity:	4.99 fps		3.16 fps	
X-Section Area:	22.66 sq ft		35.77 sq ft	
Hydraulic Radius:	0.864		1.222	
Froude Number:	0.94		0.50	
Roughness Coefficient:	0.0373		0.0743	

Structure #13 (Pond)

Headwater of 60-inch diameter culvert that drains the south perimeter channel under the perimeter road

Pond Inputs:

Initial Pool Elev:	401.00
Initial Pool:	0.03 ac-ft

Drop Inlet

Riser Diameter (in)	Riser Height (ft)	Barrel Diameter (in)	Barrel Length (ft)	Barrel Slope (%)	Manning's n	Spillway Elev
72.00	4.00	60.00	80.00	0.10	0.0240	401.00

Pond Results:

Peak Elevation:	403.17
Dewater Time:	0.52 days

*Dewatering time is calculated from peak stage to lowest spillway*

Elevation-Capacity-Discharge Table

Elevation	Area (ac)	Capacity (ac-ft)	Discharge (cfs)	Dewater Time (hrs)
395.00	0.001	0.000	0.000	
395.50	0.001	0.001	0.000	
396.00	0.002	0.001	0.000	
396.50	0.002	0.002	0.000	
397.00	0.003	0.004	0.000	
397.50	0.004	0.005	0.000	
398.00	0.004	0.007	0.000	
398.50	0.005	0.010	0.000	
399.00	0.006	0.013	0.000	
399.50	0.007	0.016	0.000	
399.70	0.007	0.017	0.000	
399.75	0.007	0.018	0.000	
399.80	0.007	0.018	0.000	
400.00	0.008	0.019	0.000	
400.50	0.009	0.024	0.000	
401.00	0.010	0.028	0.000	Spillway #1
401.50	0.031	0.038	20.659	11.45
402.00	0.062	0.061	58.434	0.70
402.50	0.105	0.102	107.349	0.10



Elevation	Area (ac)	Capacity (ac-ft)	Discharge (cfs)	Dewater Time (hrs)
403.00	0.159	0.168	165.275	
403.17	0.184	0.200	182.028	0.20 Peak Stage
403.50	0.224	0.263	215.257	
404.00	0.300	0.393	224.165	
404.50	0.394	0.566	231.945	
405.00	0.500	0.789	239.473	

**Detailed Discharge Table**

Elevation	Drop Inlet (cfs)	Combined Total Discharge (cfs)
395.00	0.000	0.000
395.50	0.000	0.000
396.00	0.000	0.000
396.50	0.000	0.000
397.00	0.000	0.000
397.50	0.000	0.000
398.00	0.000	0.000
398.50	0.000	0.000
399.00	0.000	0.000
399.50	0.000	0.000
399.70	0.000	0.000
399.75	0.000	0.000
399.80	0.000	0.000
400.00	0.000	0.000
400.50	0.000	0.000
401.00	0.000	0.000
401.50	20.659	20.659
402.00	58.434	58.434
402.50	107.349	107.349
403.00	165.275	165.275
403.50	215.257	215.257
404.00	224.165	224.165
404.50	231.945	231.945
405.00	239.473	239.473

*Structure #31 (Vegetated Channel)*

*South perimeter channels from the 60-inch diameter culvert to the junction between the north and south perimeter channels*

Trapezoidal Vegetated Channel Inputs:

Material: Tall fescue

Bottom Width (ft)	Left Sideslope Ratio	Right Sideslope Ratio	Slope (%)	Retardance Classes	Freeboard Depth (ft)	Freeboard % of Depth	Freeboard Mult. x (VxD)	Limiting Velocity (fps)
20.00	4.0:1	4.0:1	1.3	D, B				7.0

Vegetated Channel Results:

	Stability Class D w/o Freeboard	Stability Class D w/ Freeboard	Capacity Class B w/o Freeboard	Capacity Class B w/ Freeboard
Design Discharge:	182.03 cfs		182.03 cfs	
Depth:	1.35 ft		1.92 ft	
Top Width:	30.78 ft		35.33 ft	
Velocity:	5.32 fps		3.43 fps	
X-Section Area:	34.20 sq ft		53.01 sq ft	
Hydraulic Radius:	1.099		1.481	
Froude Number:	0.89		0.49	
Roughness Coefficient:	0.0340		0.0642	

Structure #24 (Null)

*E drainage area*

Structure #28 (Vegetated Channel)

*North perimeter channel - existing perimeter channel from E drainage area to NE drainage area - drains E area*

Trapezoidal Vegetated Channel Inputs:

Material: Tall fescue

Bottom Width (ft)	Left Sideslope Ratio	Right Sideslope Ratio	Slope (%)	Retardance Classes	Freeboard Depth (ft)	Freeboard % of Depth	Freeboard Mult. x (VxD)	Limiting Velocity (fps)
2.00	4.0:1	4.0:1	2.0	D, B				7.0

Vegetated Channel Results:

	Stability Class D w/o Freeboard	Stability Class D w/ Freeboard	Capacity Class B w/o Freeboard	Capacity Class B w/ Freeboard
Design Discharge:	80.57 cfs		80.57 cfs	
Depth:	1.66 ft		2.26 ft	
Top Width:	15.29 ft		20.06 ft	

	Stability Class D w/o Freeboard	Stability Class D w/ Freeboard	Capacity Class B w/o Freeboard	Capacity Class B w/ Freeboard
Velocity:	5.61 fps		3.24 fps	
X-Section Area:	14.36 sq ft		24.89 sq ft	
Hydraulic Radius:	0.915		1.208	
Froude Number:	1.02		0.51	
Roughness Coefficient:	0.0354		0.0738	

Structure #23 (Null)

*NE drainage area*

Structure #29 (Riprap Channel)

*North perimeter channel - existing perimeter channel from NE drainage area and N drainage area - drains NE and E areas*

Trapezoidal Riprap Channel Inputs:

Material: Riprap

Bottom Width (ft)}	Left Sideslope Ratio	Right Sideslope Ratio	Slope (%)	Freeboard Depth (ft)	Freeboard % of Depth	Freeboard Mult. x (VxD)
2.00	3.0:1	3.0:1	6.7			

Riprap Channel Results:

**PADER Method - Steep Slope Design**

	w/o Freeboard	w/ Freeboard
Design Discharge:	85.92 cfs	
Depth:	1.58 ft	
Top Width:	11.46 ft	
Velocity:	8.09 fps	
X-Section Area:	10.62 sq ft	
Hydraulic Radius:	0.887	
Froude Number:	1.48	
Manning's n:	0.0440	
Dmin:	3.00 in	
D50:	6.00 in	
Dmax:	9.00 in	

Structure #15 (Vegetated Channel)

*N drainage area*

Trapezoidal Vegetated Channel Inputs:

Material: Grass mixture

Bottom Width (ft)	Left Sideslope Ratio	Right Sideslope Ratio	Slope (%)	Retardance Classes	Freeboard Depth (ft)	Freeboard % of Depth	Freeboard Mult. x (VxD)	Limiting Velocity (fps)
20.00	3.0:1	3.0:1	0.3	D, B				5.0

Vegetated Channel Results:

	Stability Class D w/o Freeboard	Stability Class D w/ Freeboard	Capacity Class B w/o Freeboard	Capacity Class B w/ Freeboard
Design Discharge:	263.85 cfs		263.85 cfs	
Depth:	2.58 ft		3.56 ft	
Top Width:	35.50 ft		41.37 ft	
Velocity:	3.68 fps		2.41 fps	
X-Section Area:	71.68 sq ft		109.26 sq ft	
Hydraulic Radius:	1.973		2.570	
Froude Number:	0.46		0.26	
Roughness Coefficient:	0.0318		0.0579	

*Structure #30 (Vegetated Channel)*

*North perimeter channel - widened existing perimeter channel from N drainage area to NE drainage area - drains N, NE, and E areas*

Trapezoidal Vegetated Channel Inputs:

Material: Tall fescue

Bottom Width (ft)	Left Sideslope Ratio	Right Sideslope Ratio	Slope (%)	Retardance Classes	Freeboard Depth (ft)	Freeboard % of Depth	Freeboard Mult. x (VxD)	Limiting Velocity (fps)
12.00	4.0:1	4.0:1	0.7	D, B				7.0

Vegetated Channel Results:

	Stability Class D w/o Freeboard	Stability Class D w/ Freeboard	Capacity Class B w/o Freeboard	Capacity Class B w/ Freeboard
Design Discharge:	342.72 cfs		342.72 cfs	
Depth:	2.51 ft		3.24 ft	
Top Width:	32.04 ft		37.90 ft	
Velocity:	6.21 fps		4.24 fps	
X-Section Area:	55.16 sq ft		80.79 sq ft	
Hydraulic Radius:	1.689		2.088	

	Stability Class D w/o Freeboard	Stability Class D w/ Freeboard	Capacity Class B w/o Freeboard	Capacity Class B w/ Freeboard
Froude Number:	0.83		0.51	
Roughness Coefficient:	0.0284		0.0480	

Structure #10 (Null)

*NW drainage area*

Structure #12 (Vegetated Channel)

*North perimeter channel from NE drainage area to junction with south perimeter channel drains NW, N, NE, and N drainage areas*

Trapezoidal Vegetated Channel Inputs:

Material: Tall fescue

Bottom Width (ft)	Left Sideslope Ratio	Right Sideslope Ratio	Slope (%)	Retardance Classes	Freeboard Depth (ft)	Freeboard % of Depth	Freeboard Mult. x (VxD)	Limiting Velocity (fps)
12.00	3.0:1	3.0:1	0.7	D, B	1.00			7.0

Vegetated Channel Results:

	Stability Class D w/o Freeboard	Stability Class D w/ Freeboard	Capacity Class B w/o Freeboard	Capacity Class B w/ Freeboard
Design Discharge:	353.02 cfs		353.02 cfs	
Depth:	2.60 ft	3.60 ft	3.31 ft	4.31 ft
Top Width:	27.61 ft	33.61 ft	31.86 ft	37.86 ft
Velocity:	6.85 fps		4.86 fps	
X-Section Area:	51.54 sq ft		72.59 sq ft	
Hydraulic Radius:	1.811		2.204	
Froude Number:	0.88		0.57	
Roughness Coefficient:	0.0270		0.0434	

Structure #14 (Vegetated Channel)

*Channel at southwest corner of existing retention pond that drains the north perimeter and south perimeter channels*

Trapezoidal Vegetated Channel Inputs:

## Material: Tall fescue

Bottom Width (ft)	Left Sideslope Ratio	Right Sideslope Ratio	Slope (%)	Retardance Classes	Freeboard Depth (ft)	Freeboard % of Depth	Freeboard Mult. x (VxD)	Limiting Velocity (fps)
20.00	3.0:1	3.0:1	0.5	D, B				7.0

### Vegetated Channel Results:

	Stability Class D w/o Freeboard	Stability Class D w/ Freeboard	Capacity Class B w/o Freeboard	Capacity Class B w/ Freeboard
Design Discharge:	411.02 cfs		411.02 cfs	
Depth:	2.52 ft		3.27 ft	
Top Width:	35.15 ft		39.63 ft	
Velocity:	5.90 fps		4.21 fps	
X-Section Area:	69.63 sq ft		97.52 sq ft	
Hydraulic Radius:	1.936		2.397	
Froude Number:	0.74		0.47	
Roughness Coefficient:	0.0277		0.0448	

***Subwatershed Hydrology Detail:***

Stru #	SWS #	SWS Area (ac)	Time of Conc (hrs)	Musk K (hrs)	Musk X	Curve Number	UHS	Peak Discharge (cfs)	Runoff Volume (ac-ft)
#27	1	22.900	0.102	0.000	0.000	78.000	TR55	72.35	5.878
	$\Sigma$	<b>22.900</b>						<b>72.35</b>	<b>5.878</b>
#16	1	22.600	0.252	0.000	0.000	78.000	TR55	63.78	5.801
	$\Sigma$	<b>22.600</b>						<b>63.78</b>	<b>5.801</b>
<b>#25</b>	$\Sigma$	<b>22.600</b>						<b>63.78</b>	<b>5.801</b>
#18	1	2.800	0.088	0.000	0.000	78.000	TR55	8.85	0.719
	$\Sigma$	<b>2.800</b>						<b>8.85</b>	<b>0.719</b>
<b>#20</b>	$\Sigma$	<b>2.800</b>						<b>8.85</b>	<b>0.719</b>
<b>#26</b>	$\Sigma$	<b>2.800</b>						<b>8.85</b>	<b>0.719</b>
#17	1	16.100	0.249	0.000	0.000	78.000	TR55	45.59	4.133
	$\Sigma$	<b>16.100</b>						<b>45.59</b>	<b>4.133</b>
<b>#21</b>	$\Sigma$	<b>18.900</b>						<b>52.22</b>	<b>4.852</b>
<b>#22</b>	$\Sigma$	<b>41.500</b>						<b>112.98</b>	<b>10.653</b>
<b>#13</b>	$\Sigma$	<b>64.400</b>						<b>185.33</b>	<b>16.531</b>
<b>#31</b>	$\Sigma$	<b>64.400</b>						<b>182.03</b>	<b>16.531</b>
#24	1	50.000	1.017	0.000	0.000	78.000	TR55	80.57	12.835
	$\Sigma$	<b>50.000</b>						<b>80.57</b>	<b>12.835</b>
<b>#28</b>	$\Sigma$	<b>50.000</b>						<b>80.57</b>	<b>12.835</b>
#23	1	10.300	0.160	0.000	0.000	78.000	TR55	30.90	2.644
	$\Sigma$	<b>10.300</b>						<b>30.90</b>	<b>2.644</b>
<b>#29</b>	$\Sigma$	<b>60.300</b>						<b>85.92</b>	<b>15.479</b>
#15	1	144.000	0.818	0.000	0.000	78.000	TR55	263.85	36.964
	$\Sigma$	<b>144.000</b>						<b>263.85</b>	<b>36.964</b>
<b>#30</b>	$\Sigma$	<b>204.300</b>						<b>342.72</b>	<b>52.443</b>
#10	1	16.900	0.253	0.000	0.000	78.000	TR55	47.64	4.338
	$\Sigma$	<b>16.900</b>						<b>47.64</b>	<b>4.338</b>
<b>#12</b>	$\Sigma$	<b>221.200</b>						<b>353.02</b>	<b>56.781</b>
<b>#14</b>	$\Sigma$	<b>285.600</b>						<b>411.02</b>	<b>73.313</b>

***Subwatershed Time of Concentration Details:***

Stru #	SWS #	Land Flow Condition	Slope (%)	Vert. Dist. (ft)	Horiz. Dist. (ft)	Velocity (fps)	Time (hrs)
#10	1	3. Short grass pasture	7.50	150.00	2,000.00	2.190	0.253
<b>#10</b>	<b>1</b>	<b>Time of Concentration:</b>					<b>0.253</b>
#15	1	3. Short grass pasture	1.43	40.00	2,800.14	0.950	0.818
<b>#15</b>	<b>1</b>	<b>Time of Concentration:</b>					<b>0.818</b>
#16	1	3. Short grass pasture	6.84	130.00	1,900.00	2.090	0.252
<b>#16</b>	<b>1</b>	<b>Time of Concentration:</b>					<b>0.252</b>
#17	1	3. Short grass pasture	4.40	66.00	1,500.00	1.670	0.249
<b>#17</b>	<b>1</b>	<b>Time of Concentration:</b>					<b>0.249</b>
#18	1	3. Short grass pasture	10.00	80.00	800.00	2.520	0.088
<b>#18</b>	<b>1</b>	<b>Time of Concentration:</b>					<b>0.088</b>
#23	1	3. Short grass pasture	9.29	130.00	1,400.00	2.430	0.160
<b>#23</b>	<b>1</b>	<b>Time of Concentration:</b>					<b>0.160</b>
#24	1	3. Short grass pasture	1.62	60.00	3,700.00	1.010	1.017
<b>#24</b>	<b>1</b>	<b>Time of Concentration:</b>					<b>1.017</b>
#27	1	6. Grassed waterway	8.97	148.00	1,650.00	4.490	0.102
<b>#27</b>	<b>1</b>	<b>Time of Concentration:</b>					<b>0.102</b>



# **Maximum-Flow Design** **for the Side-Slope Terrace Channel**

## **AB Brown Type III Landfill** **January 2007 Minor Modification**

*Using the 25-year/24-hour design storm, the following calculations show that the maximum flows produced by this site are allowable for the size and configuration of the proposed side-slope terrace channels.*

DS

## ***General Information***

### ***Storm Information:***

Storm Type:	NRCS Type II
Design Storm:	25 yr - 24 hr
Rainfall Depth:	5.430 inches

**Structure Networking:**

Type	Stru #	(flows into)	Stru #	Musk. K (hrs)	Musk. X	Description
Channel	#10	==>	End	0.000	0.000	Side-slope terrace channel with a site-maximum length of 1000 feet at 2%

#10  
Chan'

***Structure Summary:***

	Immediate Contributing Area (ac)	Total Contributing Area (ac)	Peak Discharge (cfs)	Total Runoff Volume (ac-ft)
#10	2.300	2.300	6.81	0.59

**Structure Detail:**

Structure #10 (Vegetated Channel)

*Side-slope terrace channel with a site-maximum length of 1000 feet at 2%*

Triangular Vegetated Channel Inputs:

Material: Grass mixture

Left Sideslope Ratio	Right Sideslope Ratio	Slope (%)	Retardance Classes	Freeboard Depth (ft)	Freeboard % of Depth	Freeboard Mult. x (VxD)	Limiting Velocity (fps)
4.0:1	5.0:1	2.0	D, B	0.50			5.0

Vegetated Channel Results:

	Stability Class D w/o Freeboard	Stability Class D w/ Freeboard	Capacity Class B w/o Freeboard	Capacity Class B w/ Freeboard
Design Discharge:	6.81 cfs		6.81 cfs	
Depth:	0.88 ft	1.38 ft	1.40 ft	1.90 ft
Top Width:	7.93 ft	12.43 ft	12.60 ft	17.10 ft
Velocity:	1.95 fps		0.77 fps	
X-Section Area:	3.49 sq ft		8.82 sq ft	
Hydraulic Radius:	0.430		0.683	
Froude Number:	0.52		0.16	
Roughness Coefficient:	0.0615		0.2117	

***Subwatershed Hydrology Detail:***

Stru #	SWS #	SWS Area (ac)	Time of Conc (hrs)	Musk K (hrs)	Musk X	Curve Number	UHS	Peak Discharge (cfs)	Runoff Volume (ac-ft)
#10	1	2.300	0.194	0.000	0.000	78.000	TR55	6.81	0.590
$\Sigma$		<b>2.300</b>						<b>6.81</b>	<b>0.590</b>

***Subwatershed Time of Concentration Details:***

Stru #	SWS #	Land Flow Condition	Slope (%)	Vert. Dist. (ft)	Horiz. Dist. (ft)	Velocity (fps)	Time (hrs)
#10	1	3. Short grass pasture	3.86	42.50	1,100.00	1.570	0.194
<b>#10</b>	<b>1</b>	<b>Time of Concentration:</b>					<b>0.194</b>

---

**Maximum Flow Design**  
**for the Top-of-Slope Diversion Berm**

**AB Brown Type III Landfill**  
**January 2007 Minor Modification**

*Using the 25-year/24-hour design storm, the following calculations show that the maximum flows produced by this site are allowable for the size and configuration of the proposed top-of-slope diversion berms.*

DS

---

***General Information***

***Storm Information:***

Storm Type:	NRCS Type II
Design Storm:	25 yr - 24 hr
Rainfall Depth:	5.430 inches



***Structure Networking:***

Type	Stru #	(flows into)	Stru #	Musk. K (hrs)	Musk. X	Description
Channel	#12	==>	End	0.000	0.000	2% top-slope diversion berm assuming a site-maximum of 18 acres for the 5%-sloped final cover

#12  
Chan'

***Structure Summary:***

	Immediate Contributing Area (ac)	Total Contributing Area (ac)	Peak Discharge (cfs)	Total Runoff Volume (ac-ft)
#12	18.000	18.000	49.02	4.62

***Structure Detail:***

*Structure #12 (Vegetated Channel)*

*2% top-slope diversion berm assuming a site-maximum of 18 acres for the 5%-sloped final cover*

Triangular Vegetated Channel Inputs:

Material: Grass mixture

Left Sideslope Ratio	Right Sideslope Ratio	Slope (%)	Retardance Classes	Freeboard Depth (ft)	Freeboard % of Depth	Freeboard Mult. x (VxD)	Limiting Velocity (fps)
4.0:1	20.0:1	2.0	D, B				5.0

Vegetated Channel Results:

	Stability Class D w/o Freeboard	Stability Class D w/ Freeboard	Capacity Class B w/o Freeboard	Capacity Class B w/ Freeboard
Design Discharge:	49.02 cfs		49.02 cfs	
Depth:	1.17 ft		1.72 ft	
Top Width:	28.08 ft		41.38 ft	
Velocity:	2.98 fps		1.37 fps	
X-Section Area:	16.43 sq ft		35.67 sq ft	
Hydraulic Radius:	0.583		0.859	
Froude Number:	0.69		0.26	
Roughness Coefficient:	0.0492		0.1385	

***Subwatershed Hydrology Detail:***

Stru #	SWS #	SWS Area (ac)	Time of Conc (hrs)	Musk K (hrs)	Musk X	Curve Number	UHS	Peak Discharge (cfs)	Runoff Volume (ac-ft)
#12	1	18.000	0.339	0.000	0.000	78.000	TR55	49.02	4.621
<b>Σ</b>		<b>18.000</b>						<b>49.02</b>	<b>4.621</b>

***Subwatershed Time of Concentration Details:***

Stru #	SWS #	Land Flow Condition	Slope (%)	Vert. Dist. (ft)	Horiz. Dist. (ft)	Velocity (fps)	Time (hrs)
#12	1	3. Short grass pasture	2.69	43.00	1,600.00	1.310	0.339
<b>#12</b>	<b>1</b>	<b>Time of Concentration:</b>					<b>0.339</b>

---

**Maximum Flow Design**  
**for the Riprap-Lined Downdrain and**  
**Riprap-Lined Plunge Pool**

**AB Brown Type III Landfill**  
**January 2007 Minor Modification**

*Using the 25-year/24-hour design storm, the following calculations show that the maximum flows produced by this site are allowable for the size and configuration of the proposed riprap-lined downdrains and the riprap-lined plunge pool at the base of each downdrain.*

DS

---


***General Information***

***Storm Information:***

Storm Type:	NRCS Type II
Design Storm:	25 yr - 24 hr
Rainfall Depth:	5.430 inches

***Structure Networking:***

Type	Stru #	(flows into)	Stru #	Musk. K (hrs)	Musk. X	Description
Channel	#11	==>	#12	0.000	0.000	25%-sloped riprap downdrain downdrain for a site-maximum 25yr/24hr- peak flow of 72 cfs that is developed in the W sub-drainage area
Plunge Pool	#12	==>	End	0.000	0.000	Plunge pool located at end of riprap-lined downdrain - note that the velocity of downdrain at 10 fps used for the plunge pool design and also that the INDOT Class I riprap will have a conservative D50 size of abot 12 inches



***Structure Summary:***

	Immediate Contributing Area (ac)	Total Contributing Area (ac)	Peak Discharge (cfs)	Total Runoff Volume (ac-ft)
#11	22.900	22.900	72.35	5.88
#12	0.000	22.900	72.35	5.88



**Structure Detail:**

Structure #11 (Riprap Channel)

*25%-sloped riprap downdrain downdrain for a site-maximum 25yr/24hr- peak flow of 72 cfs that is developed in the W sub-drainage area*

Trapezoidal Riprap Channel Inputs:

Material: Riprap

Bottom Width (ft)}	Left Sideslope Ratio	Right Sideslope Ratio	Slope (%)	Freeboard Depth (ft)	Freeboard % of Depth	Freeboard Mult. x (VxD)
2.00	4.0:1	4.0:1	25.0			

Riprap Channel Results:

PADER Method - Steep Slope Design

	w/o Freeboard	w/ Freeboard
Design Discharge:	72.35 cfs	
Depth:	1.14 ft	
Top Width:	11.11 ft	
Velocity:	9.69 fps	
X-Section Area:	7.47 sq ft	
Hydraulic Radius:	0.655	
Froude Number:	2.08	
Manning's n:	0.0580	
Dmin:	5.00 in	
D50:	9.00 in	
Dmax:	12.00 in	

Structure #12 (Plunge Pool)

*Plunge pool located at end of riprap-lined downdrain - note that the velocity of downdrain at 10 fps used for the plunge pool design and also that the INDOT Class I riprap will have a conservative D50 size of abot 12 inches*

Plunge Pool Inputs:

Pipe Diameter (in)	Pipe Slope (%)	Pipe Outlet Elevation	Tailwater Elevation	Channel Outlet Elevation	D50 (ft)
36.00	25.00	404.20	404.10	404.00	0.63

## Plunge Pool Results:

Plunge Pool Length:	19.76 ft
Plunge Pool Width:	18.09 ft
Plunge Pool Depth (to top of rock):	4.46 ft
Froude Number:	2.47
Horiz Distance from Pipe Outlet to Center of Jet:	2.41 ft
Horiz Distance from Pipe Outlet to Center of Pool:	7.78 ft
Velocity at Pipe Outlet:	10.24 fps
Velocity at Jet Impingement:	14.32 fps

***Subwatershed Hydrology Detail:***

Stru #	SWS #	SWS Area (ac)	Time of Conc (hrs)	Musk K (hrs)	Musk X	Curve Number	UHS	Peak Discharge (cfs)	Runoff Volume (ac-ft)
#11	1	22.900	0.000	0.000	0.000	78.000	72.35	5.878	
	$\Sigma$	<b>22.900</b>						<b>72.35</b>	<b>5.878</b>
<b>#12</b>	$\Sigma$	<b>22.900</b>						<b>72.35</b>	<b>5.878</b>

Reference 2: HydroCAD Modeling Results

---

## ATC ASSOCIATES, INC.

PROJECT A.B. Brown Landfill Minor Modification

PROJECT NO. \_\_\_\_\_

Storm Water Runoff Calculations

PAGE \_\_\_\_\_

OF \_\_\_\_\_

MADE BY DS

DATE \_\_\_\_\_

3/12

CHECKED BY \_\_\_\_\_

DB

DATE \_\_\_\_\_

---

### STORM WATER RUNOFF CALCULATIONS

The erosion and stormwater control structures described in this section have been designed, as required, to limit soil erosion to less than 5 tons-per-acre-per-year and adequately convey the 25-year/24-hour storm event (5.43", IDNR 1994, attached). Soil erosion estimates are attached in a separate calculations section.

**Stormwater flows from sub-drainage areas SW, SE, NW, and NE are drained through downdrain pipes to perimeter channels.** Flows were determined for each of these proposed sub-drainage areas (SW, SE, NW, and NE - see attached figure) using the HydroCAD model developed by HydroCAD Software Solutions LLC. These sub-drainage area flows are based on drainage area, elevation change across the drainage area, flow path length, and soil cover characteristics. The resulting flows from the 25-year/24-hour storm are:

- NW area (9.4 acres at 16.0 cfs peak) drains through two 18-inch diameter drop inlets and flows through a single 18-inch diameter downdrain pipe (at about one-half full) to a riprap-lined splash pad placed in an existing channel.
- SW area (9.2 acres at 15.8 cfs peak) drains through two 18-inch diameter drop inlets and flows through a single 18-inch diameter downdrain pipe (at about one-half full) to a riprap-lined splash pad placed in an existing channel.
- SE area (8.3 acres at 15.0 cfs peak) drains through two 18-inch diameter drop inlets and flows through a single 18-inch diameter downdrain pipe (at about one-half full) to a riprap-lined splash pad placed in an existing channel.
- NE area (8.2 acres at 14.8 cfs peak) drains through two 18-inch diameter drop inlets and flows through a single 18-inch diameter downdrain pipe (at about one-half full) to a riprap-lined splash pad placed in an existing channel.

**The maximum design flows within a top-of-final-cover diversion berm occurs with sub-drainage area NW.** The top-of-final-cover diversion berms have been placed near the perimeter of the 5%-sloped top of the final cover. These channels are:

- Slopes of 2%,
- Sideslopes of 4H:1V and 20H:1V with v-shaped bottoms,
- Lengths up to 640 ft,

---

**ATC ASSOCIATES, INC.**

PROJECT **A.B. Brown Landfill Minor Modification**

PROJECT NO. \_\_\_\_\_

**Storm Water Runoff Calculations**

PAGE \_\_\_\_\_ OF \_\_\_\_\_

---

MADE BY **DS**

DATE **3/12**

CHECKED BY **DB**

DATE \_\_\_\_\_

---

- Berm heights of 2 feet at more than 200 feet from the downdrain,
- Berm heights of 4 feet within 200 feet of the downdrains, and
- Drainage Areas of up to 6.4 acres with 5% slopes.

The attached HydroCAD output shows that at the maximum area of 6.4 acres (the west portion of the NW sub-drainage area - see attached figure), this proposed berm adequately carries the 25-year/24-hour storm flow to the inlets of a pipe downdrain.

---

**ATC ASSOCIATES, INC.**

PROJECT **A.B. Brown Landfill Minor Modification**

PROJECT NO. \_\_\_\_\_

**Storm Water Runoff Calculations**

PAGE \_\_\_\_\_

OF \_\_\_\_\_

---

MADE BY **DS**

DATE **3/12**


CHECKED BY **DB**

DATE \_\_\_\_\_

---

Documentation

# RAINFALL - 25 YEAR FREQUENCY - 24 HOUR DURATION



REFERENCE  
 TECHNICAL PAPER NO. 40  
 NATIONAL WEATHER SERVICE

STATE OF INDIANA  
 DEPARTMENT OF NATURAL RESOURCES  
 DIVISION OF WATER

APRIL 1979



SOLID WASTE  
BOUNDARY

18-inch Pipe  
Downdrain

18-inch Pipe  
Downdrain

NW  
9.4 ac.


NE  
8.2 ac.

SE  
8.3 ac.

SW  
9.2 ac.




18-inch Pipe  
Downdrain

18-inch Pipe  
Downdrain



# NW Subdrainage Area

25 year / 24 hour storm on  
9.4 acres



## Routing Diagram for ABB 9.4

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net, Printed 3/20/2012  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

**ABB 9.4**

Prepared by HydroCAD SAMPLER 1-800-927-7246 [www.hydrocad.net](http://www.hydrocad.net)  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012

Page 2

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at [www.hydrocad.net](http://www.hydrocad.net). Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

**Area Listing (all nodes)**

Area (acres)	CN	Description (subcatchment-numbers)
9.400	78	(3S)
<b>9.400</b>	<b>78</b>	<b>TOTAL AREA</b>

**ABB 9.4**

Prepared by HydroCAD SAMPLER 1-800-927-7246 [www.hydrocad.net](http://www.hydrocad.net)  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012

Page 3

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at [www.hydrocad.net](http://www.hydrocad.net). Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

**Soil Listing (all nodes)**

Area (acres)	Soil Group	Subcatchment Numbers
0.000	HSG A	
0.000	HSG B	
0.000	HSG C	
0.000	HSG D	
9.400	Other	3S
<b>9.400</b>		<b>TOTAL AREA</b>

**ABB 9.4**

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at [www.hydrocad.net](http://www.hydrocad.net). Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

**Ground Covers (all nodes)**

HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
0.000	0.000	0.000	0.000	9.400	9.400		3S
<b>0.000</b>	<b>0.000</b>	<b>0.000</b>	<b>0.000</b>	<b>9.400</b>	<b>9.400</b>	<b>TOTAL AREA</b>	

**ABB 9.4**

Prepared by HydroCAD SAMPLER 1-800-927-7246 [www.hydrocad.net](http://www.hydrocad.net)  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012

Page 5

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at [www.hydrocad.net](http://www.hydrocad.net). Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

**Pipe Listing (all nodes)**

Line#	Node Number	In-Invert (feet)	Out-Invert (feet)	Length (feet)	Slope (ft/ft)	n	Diam/Width (inches)	Height (inches)	Inside-Fill (inches)
1	2R	0.00	-5.00	20.0	0.2500	0.015	15.6	0.0	0.0

**ABB 9.4**

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012

Page 6

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

Time span=5.00-35.00 hrs, dt=0.10 hrs, 301 points  
Runoff by SCS TR-20 method, UH=SCS  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Subcatchment 3S: (new Subcat)** Runoff Area=9.400 ac 0.00% Impervious Runoff Depth=3.08"  
Flow Length=300' Slope=0.0500 '/' Tc=20.3 min CN=78 Runoff=31.23 cfs 2.413 af

**Reach 2R: (new Reach)** Avg. Flow Depth=0.66' Max Vel=23.56 fps Inflow=16.02 cfs 2.413 af  
15.6" Round Pipe n=0.015 L=20.0' S=0.2500 '/' Capacity=31.08 cfs Outflow=16.02 cfs 2.413 af

**Pond 1P: (new Pond)** Peak Elev=2.22' Storage=19,265 cf Inflow=31.23 cfs 2.413 af  
Outflow=16.02 cfs 2.413 af

**Total Runoff Area = 9.400 ac Runoff Volume = 2.413 af Average Runoff Depth = 3.08"**  
**100.00% Pervious = 9.400 ac 0.00% Impervious = 0.000 ac**

**ABB 9.4**

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net  
 HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012

Page 7

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

**Summary for Subcatchment 3S: (new Subcat)**

Runoff = 31.23 cfs @ 12.13 hrs, Volume= 2.413 af, Depth= 3.08"


Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-35.00 hrs, dt= 0.10 hrs  
 Type II 24-hr Rainfall=5.43"

Area (ac)	CN	Description
* 9.400	78	
9.400		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
20.3	300	0.0500	0.25		Sheet Flow, n= 0.200 P2= 3.30"

**Subcatchment 3S: (new Subcat)**

Hydrograph





**ABB 9.4**

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012

Page 8

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

**Summary for Reach 2R: (new Reach)**

[52] Hint: Inlet/Outlet conditions not evaluated

[65] Warning: Inlet elevation not specified


[90] Warning: Qout&gt;Qin may require Finer Routing or smaller dt

Inflow Area = 9.400 ac, 0.00% Impervious, Inflow Depth = 3.08"  
Inflow = 16.02 cfs @ 12.35 hrs, Volume= 2.413 af  
Outflow = 16.02 cfs @ 12.35 hrs, Volume= 2.413 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 5.00-35.00 hrs, dt= 0.10 hrs  
Max. Velocity= 23.56 fps, Min. Travel Time= 0.0 min  
Avg. Velocity = 10.10 fps, Avg. Travel Time= 0.0 min

Peak Storage= 14 cf @ 12.35 hrs  
Average Depth at Peak Storage= 0.66'  
Bank-Full Depth= 1.30' Flow Area= 1.3 sf, Capacity= 31.08 cfs

15.6" Round Pipe  
n= 0.015 Corrugated PE, smooth interior  
Length= 20.0' Slope= 0.2500 1'  
Inlet Invert= 0.00', Outlet Invert= -5.00'



**ABB 9.4**

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC


Printed 3/20/2012

Page 9

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

**Reach 2R: (new Reach)**

Hydrograph



**ABB 9.4**

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012

Page 10

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

**Summary for Pond 1P: (new Pond)**

Inflow Area = 9.400 ac, 0.00% Impervious, Inflow Depth = 3.08"  
 Inflow = 31.23 cfs @ 12.13 hrs, Volume= 2.413 af  
 Outflow = 16.02 cfs @ 12.35 hrs, Volume= 2.413 af, Atten= 49%, Lag= 13.0 min  
 Primary = 16.02 cfs @ 12.35 hrs, Volume= 2.413 af

Routing by Dyn-Stor-Ind method, Time Span= 5.00-35.00 hrs, dt= 0.10 hrs  
 Peak Elev= 2.22' @ 12.35 hrs Surf.Area= 17,380 sf Storage= 19,265 cf

Plug-Flow detention time= 9.4 min calculated for 2.405 af (100% of inflow)  
 Center-of-Mass det. time= 9.4 min ( 843.0 - 833.6 )

Volume	Invert	Avail.Storage	Storage Description
#1	0.00'	62,724 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
0.00	2	0	0
4.00	31,360	62,724	62,724

Device	Routing	Invert	Outlet Devices
#1	Primary	0.01'	<b>15.6" Horiz. Orifice/Grate</b> C= 0.600 Limited to weir flow at low heads
#2	Primary	0.01'	<b>15.6" Vert. Orifice/Grate</b> C= 0.600

**Primary OutFlow** Max=15.88 cfs @ 12.35 hrs HW=2.20' TW=0.66' (Dynamic Tailwater)

1=Orifice/Grate (Orifice Controls 7.94 cfs @ 5.98 fps)  
 2=Orifice/Grate (Orifice Controls 7.94 cfs @ 5.98 fps)

**ABB 9.4**

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC


Printed 3/20/2012

Page 11

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.




**Pond 1P: (new Pond)**

Hydrograph



# SW Subdrainage Area

25 year/24 hour storm on.  
9.2 acres



## Routing Diagram for ABB 9.2

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net, Printed 3/20/2012  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

**ABB 9.2**

Prepared by HydroCAD SAMPLER 1-800-927-7246 [www.hydrocad.net](http://www.hydrocad.net)  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012

Page 2

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at [www.hydrocad.net](http://www.hydrocad.net). Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

**Area Listing (all nodes)**

Area (acres)	CN	Description (subcatchment-numbers)
9.200	78	cayuga (3S)
<b>9.200</b>	<b>78</b>	<b>TOTAL AREA</b>

**ABB 9.2**

Prepared by HydroCAD SAMPLER 1-800-927-7246 [www.hydrocad.net](http://www.hydrocad.net)  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012

Page 3

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at [www.hydrocad.net](http://www.hydrocad.net). Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

**Soil Listing (all nodes)**

Area (acres)	Soil Group	Subcatchment Numbers
0.000	HSG A	
0.000	HSG B	
0.000	HSG C	
0.000	HSG D	
9.200	Other	3S
<b>9.200</b>		<b>TOTAL AREA</b>

**ABB 9.2**

Prepared by HydroCAD SAMPLER 1-800-927-7246 [www.hydrocad.net](http://www.hydrocad.net)  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012

Page 4

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at [www.hydrocad.net](http://www.hydrocad.net). Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

**Ground Covers (all nodes)**

HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
0.000	0.000	0.000	0.000	9.200	9.200	cayuga	3S
<b>0.000</b>	<b>0.000</b>	<b>0.000</b>	<b>0.000</b>	<b>9.200</b>	<b>9.200</b>	<b>TOTAL AREA</b>	



**ABB 9.2**

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at [www.hydrocad.net](http://www.hydrocad.net). Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

**Pipe Listing (all nodes)**

Line#	Node Number	In-Invert (feet)	Out-Invert (feet)	Length (feet)	Slope (ft/ft)	n	Diam/Width (inches)	Height (inches)	Inside-Fill (inches)
1	2R	0.00	-5.00	20.0	0.2500	0.015	15.6	0.0	0.0

**ABB 9.2**

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012

Page 6

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

Time span=5.00-35.00 hrs, dt=0.10 hrs, 301 points

Runoff by SCS TR-20 method, UH=SCS

Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Subcatchment 3S: (new Subcat)**

Runoff Area=9.200 ac 0.00% Impervious Runoff Depth=3.08"

Flow Length=300' Slope=0.0500 '/' Tc=20.3 min CN=78 Runoff=30.57 cfs 2.362 af

**Reach 2R: (new Reach)**

Avg. Flow Depth=0.66' Max Vel=23.50 fps Inflow=15.84 cfs 2.362 af

15.6" Round Pipe n=0.015 L=20.0' S=0.2500 '/' Capacity=31.08 cfs Outflow=15.84 cfs 2.362 af

**Pond 1P: (new Pond)**

Peak Elev=2.18' Storage=18,630 cf Inflow=30.57 cfs 2.362 af

Outflow=15.84 cfs 2.362 af

**Total Runoff Area = 9.200 ac Runoff Volume = 2.362 af Average Runoff Depth = 3.08"**  
**100.00% Pervious = 9.200 ac 0.00% Impervious = 0.000 ac**

**ABB 9.2**

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012

Page 7

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

**Summary for Subcatchment 3S: (new Subcat)**

Runoff = 30.57 cfs @ 12.13 hrs, Volume= 2.362 af, Depth= 3.08"


Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-35.00 hrs, dt= 0.10 hrs  
Type II 24-hr Rainfall=5.43"

Area (ac)	CN	Description
* 9.200	78	cayuga
9.200		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
20.3	300	0.0500	0.25		Sheet Flow, n= 0.200 P2= 3.30"

**Subcatchment 3S: (new Subcat)**

Hydrograph



**ABB 9.2**

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012

Page 8

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

**Summary for Reach 2R: (new Reach)**

[52] Hint: Inlet/Outlet conditions not evaluated

[65] Warning: Inlet elevation not specified


[90] Warning: Qout&gt;Qin may require Finer Routing or smaller dt

Inflow Area = 9.200 ac, 0.00% Impervious, Inflow Depth = 3.08"  
Inflow = 15.84 cfs @ 12.34 hrs, Volume= 2.362 af  
Outflow = 15.84 cfs @ 12.34 hrs, Volume= 2.362 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 5.00-35.00 hrs, dt= 0.10 hrs  
Max. Velocity= 23.50 fps, Min. Travel Time= 0.0 min  
Avg. Velocity = 10.08 fps, Avg. Travel Time= 0.0 min

Peak Storage= 13 cf @ 12.34 hrs  
Average Depth at Peak Storage= 0.66'  
Bank-Full Depth= 1.30' Flow Area= 1.3 sf, Capacity= 31.08 cfs

15.6" Round Pipe  
n= 0.015 Corrugated PE, smooth interior  
Length= 20.0' Slope= 0.2500 '/  
Inlet Invert= 0.00', Outlet Invert= -5.00'



**ABB 9.2**

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC


Printed 3/20/2012

Page 9

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

**Reach 2R: (new Reach)**

Hydrograph



**ABB 9.2**

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012

Page 10

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

**Summary for Pond 1P: (new Pond)**

Inflow Area = 9.200 ac, 0.00% Impervious, Inflow Depth = 3.08"  
 Inflow = 30.57 cfs @ 12.13 hrs, Volume= 2.362 af  
 Outflow = 15.84 cfs @ 12.34 hrs, Volume= 2.362 af, Atten= 48%, Lag= 12.8 min  
 Primary = 15.84 cfs @ 12.34 hrs, Volume= 2.362 af

Routing by Dyn-Stor-Ind method, Time Span= 5.00-35.00 hrs, dt= 0.10 hrs  
 Peak Elev= 2.18' @ 12.35 hrs Surf.Area= 17,089 sf Storage= 18,630 cf

Plug-Flow detention time= 9.2 min calculated for 2.354 af (100% of inflow)  
 Center-of-Mass det. time= 9.2 min ( 842.8 - 833.6 )

Volume	Invert	Avail.Storage	Storage Description
#1	0.00'	62,710 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
0.00	2	0	0
4.00	31,353	62,710	62,710

Device	Routing	Invert	Outlet Devices
#1	Primary	0.01'	<b>15.6" Horiz. Orifice/Grate</b> C= 0.600 Limited to weir flow at low heads
#2	Primary	0.01'	<b>15.6" Vert. Orifice/Grate</b> C= 0.600

Primary OutFlow Max=15.70 cfs @ 12.34 hrs HW=2.17' TW=0.65' (Dynamic Tailwater)

1=Orifice/Grate (Orifice Controls 7.86 cfs @ 5.92 fps)  
 2=Orifice/Grate (Orifice Controls 7.85 cfs @ 5.91 fps)

**ABB 9.2**

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net

Printed 3/20/2012


HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Page 11

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.



**Pond 1P: (new Pond)**

Hydrograph



# SE Subdrainage Area

25 year/24 hour storm on  
8.3 acres





**ABB 8.3**

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at [www.hydrocad.net](http://www.hydrocad.net). Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

**Area Listing (all nodes)**

Area (acres)	CN	Description (subcatchment-numbers)
8.300	78	cayuga (3S)
<b>8.300</b>	<b>78</b>	<b>TOTAL AREA</b>

**ABB 8.3**

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at [www.hydrocad.net](http://www.hydrocad.net). Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

**Soil Listing (all nodes)**

Area (acres)	Soil Group	Subcatchment Numbers
0.000	HSG A	
0.000	HSG B	
0.000	HSG C	
0.000	HSG D	
8.300	Other	3S
<b>8.300</b>		<b>TOTAL AREA</b>

**ABB 8.3**

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at [www.hydrocad.net](http://www.hydrocad.net). Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

**Ground Covers (all nodes)**

HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
0.000	0.000	0.000	0.000	8.300	8.300	cayuga	3S
<b>0.000</b>	<b>0.000</b>	<b>0.000</b>	<b>0.000</b>	<b>8.300</b>	<b>8.300</b>	<b>TOTAL AREA</b>	

**ABB 8.3**

Prepared by HydroCAD SAMPLER 1-800-927-7246 [www.hydrocad.net](http://www.hydrocad.net)  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012

Page 5

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at [www.hydrocad.net](http://www.hydrocad.net). Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

**Pipe Listing (all nodes)**

Line#	Node Number	In-Invert (feet)	Out-Invert (feet)	Length (feet)	Slope (ft/ft)	n	Diam/Width (inches)	Height (inches)	Inside-Fill (inches)
1	2R	0.00	-5.00	20.0	0.2500	0.015	15.6	0.0	0.0

**ABB 8.3**

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012

Page 6

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

Time span=5.00-35.00 hrs, dt=0.10 hrs, 301 points  
Runoff by SCS TR-20 method, UH=SCS  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Subcatchment 3S: (new Subcat)** Runoff Area=8.300 ac 0.00% Impervious Runoff Depth=3.08"  
Flow Length=300' Slope=0.0500 '/' Tc=20.3 min CN=78 Runoff=27.58 cfs 2.131 af

**Reach 2R: (new Reach)** Avg. Flow Depth=0.64' Max Vel=23.19 fps Inflow=15.00 cfs 2.131 af  
15.6" Round Pipe n=0.015 L=20.0' S=0.2500 '/' Capacity=31.08 cfs Outflow=15.00 cfs 2.131 af

**Pond 1P: (new Pond)** Peak Elev=2.02' Storage=15,997 cf Inflow=27.58 cfs 2.131 af  
Outflow=15.00 cfs 2.131 af

**Total Runoff Area = 8.300 ac Runoff Volume = 2.131 af Average Runoff Depth = 3.08"**  
**100.00% Pervious = 8.300 ac 0.00% Impervious = 0.000 ac**

**ABB 8.3**

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012

Page 7

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

**Summary for Subcatchment 3S: (new Subcat)**

Runoff = 27.58 cfs @ 12.13 hrs, Volume= 2.131 af, Depth= 3.08"


Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-35.00 hrs, dt= 0.10 hrs  
Type II 24-hr Rainfall=5.43"

Area (ac)	CN	Description
* 8.300	78	cayuga
8.300		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
20.3	300	0.0500	0.25		Sheet Flow, n= 0.200 P2= 3.30"

**Subcatchment 3S: (new Subcat)**

Hydrograph



**ABB 8.3**

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012

Page 8

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

**Summary for Reach 2R: (new Reach)**

[52] Hint: Inlet/Outlet conditions not evaluated

[65] Warning: Inlet elevation not specified


[90] Warning: Qout>Qin may require Finer Routing or smaller dt

Inflow Area = 8.300 ac, 0.00% Impervious, Inflow Depth = 3.08"  
Inflow = 15.00 cfs @ 12.34 hrs, Volume= 2.131 af  
Outflow = 15.00 cfs @ 12.33 hrs, Volume= 2.131 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 5.00-35.00 hrs, dt= 0.10 hrs  
Max. Velocity= 23.19 fps, Min. Travel Time= 0.0 min  
Avg. Velocity = 9.72 fps, Avg. Travel Time= 0.0 min

Peak Storage= 13 cf @ 12.33 hrs  
Average Depth at Peak Storage= 0.64'  
Bank-Full Depth= 1.30' Flow Area= 1.3 sf, Capacity= 31.08 cfs

15.6" Round Pipe  
n= 0.015 Corrugated PE, smooth interior  
Length= 20.0' Slope= 0.2500 '/'  
Inlet Invert= 0.00', Outlet Invert= -5.00'



**ABB 8.3**

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC


Printed 3/20/2012

Page 9

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

**Reach 2R: (new Reach)**

Hydrograph





**ABB 8.3**

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012

Page 10

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

**Summary for Pond 1P: (new Pond)**

Inflow Area = 8.300 ac, 0.00% Impervious, Inflow Depth = 3.08"  
 Inflow = 27.58 cfs @ 12.13 hrs, Volume= 2.131 af  
 Outflow = 15.00 cfs @ 12.34 hrs, Volume= 2.131 af, Atten= 46%, Lag= 12.3 min  
 Primary = 15.00 cfs @ 12.34 hrs, Volume= 2.131 af

Routing by Dyn-Stor-Ind method, Time Span= 5.00-35.00 hrs, dt= 0.10 hrs  
 Peak Elev= 2.02' @ 12.34 hrs Surf.Area= 15,835 sf Storage= 15,997 cf

Plug-Flow detention time= 8.4 min calculated for 2.131 af (100% of inflow)  
 Center-of-Mass det. time= 8.4 min ( 842.0 - 833.6 )

Volume	Invert	Avail.Storage	Storage Description
#1	0.00'	62,710 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
0.00	2	0	0
4.00	31,353	62,710	62,710

Device	Routing	Invert	Outlet Devices
#1	Primary	0.01'	<b>15.6" Horiz. Orifice/Grate</b> C= 0.600 Limited to weir flow at low heads
#2	Primary	0.01'	<b>15.6" Vert. Orifice/Grate</b> C= 0.600

**Primary OutFlow** Max=14.87 cfs @ 12.34 hrs HW=2.00' TW=0.63' (Dynamic Tailwater)

↑ 1=Orifice/Grate (Orifice Controls 7.47 cfs @ 5.63 fps)

└ 2=Orifice/Grate (Orifice Controls 7.40 cfs @ 5.57 fps)

**ABB 8.3**

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net

Printed 3/20/2012


HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Page 11

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.



**Pond 1P: (new Pond)**

Hydrograph



# NE Subdrainage Area

25 year / 24 hour storm on  
8.2 acres



## Routing Diagram for ABB 8.2

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net, Printed 3/20/2012  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

**ABB 8.2**

Prepared by HydroCAD SAMPLER 1-800-927-7246 [www.hydrocad.net](http://www.hydrocad.net)  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012

Page 2

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at [www.hydrocad.net](http://www.hydrocad.net). Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

**Area Listing (all nodes)**

Area (acres)	CN	Description (subcatchment-numbers)
8.200	78	cayuga (3S)
8.200	78	<b>TOTAL AREA</b>

**ABB 8.2**

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at [www.hydrocad.net](http://www.hydrocad.net). Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

**Soil Listing (all nodes)**

Area (acres)	Soil Group	Subcatchment Numbers
0.000	HSG A	
0.000	HSG B	
0.000	HSG C	
0.000	HSG D	
8.200	Other	3S
<b>8.200</b>		<b>TOTAL AREA</b>

**ABB 8.2**

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

**Ground Covers (all nodes)**

HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
0.000	0.000	0.000	0.000	8.200	8.200	cayuga	3S
<b>0.000</b>	<b>0.000</b>	<b>0.000</b>	<b>0.000</b>	<b>8.200</b>	<b>8.200</b>	<b>TOTAL AREA</b>	

**ABB 8.2**

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at [www.hydrocad.net](http://www.hydrocad.net). Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

**Pipe Listing (all nodes)**

Line#	Node Number	In-Invert (feet)	Out-Invert (feet)	Length (feet)	Slope (ft/ft)	n	Diam/Width (inches)	Height (inches)	Inside-Fill (inches)
1	2R	0.00	-5.00	20.0	0.2500	0.015	15.6	0.0	0.0

**ABB 8.2**

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012

Page 6

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

Time span=5.00-35.00 hrs, dt=0.10 hrs, 301 points  
Runoff by SCS TR-20 method, UH=SCS  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Subcatchment 3S: (new Subcat)** Runoff Area=8.200 ac 0.00% Impervious Runoff Depth=3.08"  
Flow Length=300' Slope=0.0500 '/' Tc=20.3 min CN=78 Runoff=27.24 cfs 2.105 af

**Reach 2R: (new Reach)** Avg. Flow Depth=0.64' Max Vel=23.20 fps Inflow=14.79 cfs 2.105 af  
15.6" Round Pipe n=0.015 L=20.0' S=0.2500 '/' Capacity=31.08 cfs Outflow=14.99 cfs 2.108 af

**Pond 1P: (new Pond)** Peak Elev=1.96' Storage=14,993 cf Inflow=27.24 cfs 2.105 af  
Outflow=14.79 cfs 2.105 af

**Total Runoff Area = 8.200 ac Runoff Volume = 2.105 af Average Runoff Depth = 3.08"**  
**100.00% Pervious = 8.200 ac 0.00% Impervious = 0.000 ac**



**ABB 8.2**

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net  
 HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012

Page 7

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

**Summary for Subcatchment 3S: (new Subcat)**

Runoff = 27.24 cfs @ 12.13 hrs, Volume= 2.105 af, Depth= 3.08"


Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-35.00 hrs, dt= 0.10 hrs  
 Type II 24-hr Rainfall=5.43"

Area (ac)	CN	Description
* 8.200	78	cayuga
8.200		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
20.3	300	0.0500	0.25		Sheet Flow, n= 0.200 P2= 3.30"

**Subcatchment 3S: (new Subcat)**

Hydrograph



## ABB 8.2

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012  
Page 8

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

### Summary for Reach 2R: (new Reach)

[52] Hint: Inlet/Outlet conditions not evaluated

[65] Warning: Inlet elevation not specified

[90] Warning: Qout>Qin may require Finer Routing or smaller dt


[80] Warning: Exceeded Pond 1P by 0.06' @ 18.40 hrs (1.58 cfs 0.403 af)

Inflow Area = 8.200 ac, 0.00% Impervious, Inflow Depth = 3.08"  
Inflow = 14.79 cfs @ 12.33 hrs, Volume= 2.105 af  
Outflow = 14.99 cfs @ 12.31 hrs, Volume= 2.108 af, Atten= 0%, Lag= 0.0 min

Routing by Dyn-Stor-Ind method, Time Span= 5.00-35.00 hrs, dt= 0.10 hrs  
Max. Velocity= 23.20 fps, Min. Travel Time= 0.0 min  
Avg. Velocity= 9.29 fps, Avg. Travel Time= 0.0 min

Peak Storage= 13 cf @ 12.31 hrs  
Average Depth at Peak Storage= 0.64'  
Bank-Full Depth= 1.30' Flow Area= 1.3 sf, Capacity= 31.08 cfs

15.6" Round Pipe  
n= 0.015 Corrugated PE, smooth interior  
Length= 20.0' Slope= 0.2500 1'  
Inlet Invert= 0.00', Outlet Invert= -5.00'



**ABB 8.2**

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net

Printed 3/20/2012


HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Page 9

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

**Reach 2R: (new Reach)**

Hydrograph



**ABB 8.2**

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012

Page 10

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

**Summary for Pond 1P: (new Pond)**

[87] Warning: Oscillations may require Finer Routing or smaller dt

Inflow Area = 8.200 ac, 0.00% Impervious, Inflow Depth = 3.08"  
 Inflow = 27.24 cfs @ 12.13 hrs, Volume= 2.105 af  
 Outflow = 14.79 cfs @ 12.33 hrs, Volume= 2.105 af, Atten= 46%, Lag= 11.7 min  
 Primary = 14.79 cfs @ 12.33 hrs, Volume= 2.105 af

Routing by Dyn-Stor-Ind method, Time Span= 5.00-35.00 hrs, dt= 0.10 hrs  
 Peak Elev= 1.96' @ 12.34 hrs Surf.Area= 15,330 sf Storage= 14,993 cf

Plug-Flow detention time= (not calculated: outflow precedes inflow)  
 Center-of-Mass det. time= 7.6 min ( 841.2 - 833.6 )

Volume	Invert	Avail.Storage	Storage Description
#1	0.00'	62,710 cf	<b>Custom Stage Data (Prismatic) Listed below (Recalc)</b>

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
0.00	2	0	0
4.00	31,353	62,710	62,710

Device	Routing	Invert	Outlet Devices
#1	Primary	0.01'	<b>15.6" Horiz. Orifice/Grate</b> C= 0.600 Limited to weir flow at low heads
#2	Primary	0.01'	<b>15.6" Horiz. Orifice/Grate</b> C= 0.600 Limited to weir flow at low heads

**Primary OutFlow** Max=14.60 cfs @ 12.33 hrs HW=1.94' TW=0.63' (Dynamic Tailwater)

↑ 1=Orifice/Grate (Orifice Controls 7.30 cfs @ 5.50 fps)  
 ↓ 2=Orifice/Grate (Orifice Controls 7.30 cfs @ 5.50 fps)

**ABB 8.2**

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC


Printed 3/20/2012

Page 11

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.


**Pond 1P: (new Pond)**

Hydrograph





W portion of NW Subdrainage Area

25 year / 24 hour storm on  
6.4 acres



(new Subcat)



(new Reach)

Top-of-Landfill  
Stormwater  
Diversion Berm  
Channel



**Routing Diagram for ABB 6.4**

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net, Printed 3/20/2012  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

**ABB 6.4**

Prepared by HydroCAD SAMPLER 1-800-927-7246 [www.hydrocad.net](http://www.hydrocad.net)  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012

Page 2

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at [www.hydrocad.net](http://www.hydrocad.net). Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

**Area Listing (all nodes)**

Area (acres)	CN	Description (subcatchment-numbers)
6.400	78	(3S)
<b>6.400</b>	<b>78</b>	<b>TOTAL AREA</b>

**ABB 6.4**

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

**Soil Listing (all nodes)**

Area (acres)	Soil Group	Subcatchment Numbers
0.000	HSG A	
0.000	HSG B	
0.000	HSG C	
0.000	HSG D	
6.400	Other	3S
<b>6.400</b>		<b>TOTAL AREA</b>



**ABB 6.4**

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at [www.hydrocad.net](http://www.hydrocad.net). Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

**Ground Covers (all nodes)**

HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
0.000	0.000	0.000	0.000	6.400	6.400		3S
<b>0.000</b>	<b>0.000</b>	<b>0.000</b>	<b>0.000</b>	<b>6.400</b>	<b>6.400</b>	<b>TOTAL AREA</b>	

**ABB 6.4**

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012

Page 5

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

Time span=5.00-35.00 hrs, dt=0.10 hrs, 301 points  
Runoff by SCS TR-20 method, UH=SCS  
Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Subcatchment 3S: (new Subcat)** Runoff Area=6.400 ac 0.00% Impervious Runoff Depth=3.08"  
Flow Length=300' Slope=0.0500 '/' Tc=20.3 min CN=78 Runoff=21.26 cfs 1.643 af

**Reach 2R: (new Reach)** Avg. Flow Depth=0.76' Max Vel=3.12 fps Inflow=21.26 cfs 1.643 af  
n=0.035 L=540.0' S=0.0200 '/' Capacity=1,744.31 cfs Outflow=20.54 cfs 1.643 af

**Total Runoff Area = 6.400 ac Runoff Volume = 1.643 af Average Runoff Depth = 3.08"**  
**100.00% Pervious = 6.400 ac 0.00% Impervious = 0.000 ac**

**ABB 6.4**

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net

Printed 3/20/2012

HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Page 6

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

**Summary for Subcatchment 3S: (new Subcat)**

Runoff = 21.26 cfs @ 12.13 hrs, Volume= 1.643 af, Depth= 3.08"


Runoff by SCS TR-20 method, UH=SCS, Time Span= 5.00-35.00 hrs, dt= 0.10 hrs  
Type II 24-hr Rainfall=5.43"

Area (ac)	CN	Description
* 6.400	78	
6.400		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
20.3	300	0.0500	0.25		Sheet Flow, n= 0.200 P2= 3.30"

**Subcatchment 3S: (new Subcat)**

Hydrograph



Runoff

**ABB 6.4**

Type II 24-hr Rainfall=5.43"

Prepared by HydroCAD SAMPLER 1-800-927-7246 www.hydrocad.net  
HydroCAD® 10.00 Sampler s/n S14894 © 2011 HydroCAD Software Solutions LLC

Printed 3/20/2012

Page 7

This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

---

**Summary for Reach 2R: (new Reach)**

[65] Warning: Inlet elevation not specified

Inflow Area = 6.400 ac, 0.00% Impervious, Inflow Depth = 3.08"  
Inflow = 21.26 cfs @ 12.13 hrs, Volume= 1.643 af  
Outflow = 20.54 cfs @ 12.18 hrs, Volume= 1.643 af, Atten= 3%, Lag= 2.9 min

Routing by Dyn-Stor-Ind method, Time Span= 5.00-35.00 hrs, dt= 0.10 hrs  
Max. Velocity= 3.12 fps, Min. Travel Time= 2.9 min  
Avg. Velocity = 1.19 fps, Avg. Travel Time= 7.5 min

Peak Storage= 3,552 cf @ 12.18 hrs  
Average Depth at Peak Storage= 0.76'  
Bank-Full Depth= 4.00' Flow Area= 184.0 sf, Capacity= 1,744.31 cfs


0.00' x 4.00' deep channel, n= 0.035 High grass  
Side Slope Z-value= 20.0 3.0 '/' Top Width= 92.00'  
Length= 540.0' Slope= 0.0200 '/'  
Inlet Invert= 0.00', Outlet Invert= -10.80'



This report was prepared with the free HydroCAD SAMPLER, which is licensed for evaluation and educational use only. For actual design or modeling applications you must use a full version of HydroCAD which may be purchased at www.hydrocad.net. Full programs also include complete printed documentation, technical support, training materials, and additional features which are essential for actual design work.

### Reach 2R: (new Reach)

Hydrograph



Reference 3: USDA TR-55



**United States  
Department of  
Agriculture**

Natural  
Resources  
Conservation  
Service

Conservation  
Engineering  
Division

Technical  
Release 55

June 1986

# Urban Hydrology for Small Watersheds

## TR-55

### SCS runoff curve number method

The SCS Runoff Curve Number (CN) method is described in detail in NEH-4 (SCS 1985). The SCS runoff equation is

$$Q = \frac{(P - I_a)^2}{(P - I_a) + S} \quad [\text{eq. 2-1}]$$

where

- Q = runoff (in)
- P = rainfall (in)
- S = potential maximum retention after runoff begins (in) and
- I<sub>a</sub> = initial abstraction (in)

Initial abstraction (I<sub>a</sub>) is all losses before runoff begins. It includes water retained in surface depressions, water intercepted by vegetation, evaporation, and infiltration. I<sub>a</sub> is highly variable but generally is correlated with soil and cover parameters. Through studies of many small agricultural watersheds, I<sub>a</sub> was found to be approximated by the following empirical equation:

$$I_a = 0.2S \quad [\text{eq. 2-2}]$$

By removing I<sub>a</sub> as an independent parameter, this approximation allows use of a combination of S and P to produce a unique runoff amount. Substituting equation 2-2 into equation 2-1 gives:

$$Q = \frac{(P - 0.2S)^2}{(P + 0.8S)} \quad [\text{eq. 2-3}]$$

S is related to the soil and cover conditions of the watershed through the CN. CN has a range of 0 to 100, and S is related to CN by:

$$S = \frac{1000}{\text{CN}} - 10 \quad [\text{eq. 2-4}]$$

Figure 2-1 and table 2-1 solve equations 2-3 and 2-4 for a range of CN's and rainfall.

### Factors considered in determining runoff curve numbers

The major factors that determine CN are the hydrologic soil group (HSG), cover type, treatment, hydrologic condition, and antecedent runoff condition (ARC). Another factor considered is whether impervious areas outlet directly to the drainage system (connected) or whether the flow spreads over pervious areas before entering the drainage system (unconnected). Figure 2-2 is provided to aid in selecting the appropriate figure or table for determining curve numbers.

CN's in table 2-2 (*a* to *d*) represent average antecedent runoff condition for urban, cultivated agricultural, other agricultural, and arid and semiarid rangeland uses. Table 2-2 assumes impervious areas are directly connected. The following sections explain how to determine CN's and how to modify them for urban conditions.

### Hydrologic soil groups

Infiltration rates of soils vary widely and are affected by subsurface permeability as well as surface intake rates. Soils are classified into four HSG's (A, B, C, and D) according to their minimum infiltration rate, which is obtained for bare soil after prolonged wetting. Appendix A defines the four groups and provides a list of most of the soils in the United States and their group classification. The soils in the area of interest may be identified from a soil survey report, which can be obtained from local SCS offices or soil and water conservation district offices.

Most urban areas are only partially covered by impervious surfaces: the soil remains an important factor in runoff estimates. Urbanization has a greater effect on runoff in watersheds with soils having high infiltration rates (sands and gravels) than in watersheds predominantly of silts and clays, which generally have low infiltration rates.

Any disturbance of a soil profile can significantly change its infiltration characteristics. With urbanization, native soil profiles may be mixed or removed or fill material from other areas may be introduced. Therefore, a method based on soil texture is given in appendix A for determining the HSG classification for disturbed soils.



Manning's equation is:

$$V = \frac{1.49r^{\frac{2}{3}}s^{\frac{1}{2}}}{n} \quad [\text{eq. 3-4}]$$

where:

- V = average velocity (ft/s)
- r = hydraulic radius (ft) and is equal to  $a/p_w$
- a = cross sectional flow area (ft<sup>2</sup>)
- $p_w$  = wetted perimeter (ft)
- s = slope of the hydraulic grade line (channel slope, ft/ft)
- n = Manning's roughness coefficient for open channel flow.

Manning's n values for open channel flow can be obtained from standard textbooks such as Chow (1959) or Linsley et al. (1982). After average velocity is computed using equation 3-4,  $T_t$  for the channel segment can be estimated using equation 3-1.

### Reservoirs or lakes

Sometimes it is necessary to estimate the velocity of flow through a reservoir or lake at the outlet of a watershed. This travel time is normally very small and can be assumed as zero.

### Limitations

- Manning's kinematic solution should not be used for sheet flow longer than 300 feet. Equation 3-3 was developed for use with the four standard rainfall intensity-duration relationships.
- In watersheds with storm sewers, carefully identify the appropriate hydraulic flow path to estimate  $T_c$ . Storm sewers generally handle only a small portion of a large event. The rest of the peak flow travels by streets, lawns, and so on, to the outlet. Consult a standard hydraulics textbook to determine average velocity in pipes for either pressure or nonpressure flow.
- The minimum  $T_c$  used in TR-55 is 0.1 hour.


- A culvert or bridge can act as a reservoir outlet if there is significant storage behind it. The procedures in TR-55 can be used to determine the peak flow upstream of the culvert. Detailed storage routing procedures should be used to determine the outflow through the culvert.

### Example 3-1

The sketch below shows a watershed in Dyer County, northwestern Tennessee. The problem is to compute  $T_c$  at the outlet of the watershed (point D). The 2-year 24-hour rainfall depth is 3.6 inches. All three types of flow occur from the hydraulically most distant point (A) to the point of interest (D). To compute  $T_c$ , first determine  $T_t$  for each segment from the following information:

Segment AB: Sheet flow; dense grass; slope ( $s$ ) = 0.01 ft/ft; and length ( $L$ ) = 100 ft. Segment BC: Shallow concentrated flow; unpaved;  $s$  = 0.01 ft/ft; and  $L$  = 1,400 ft. Segment CD: Channel flow; Manning's  $n$  = .05; flow area ( $a$ ) = 27 ft<sup>2</sup>; wetted perimeter ( $p_w$ ) = 28.2 ft;  $s$  = 0.005 ft/ft; and  $L$  = 7,300 ft.

See figure 3-2 for the computations made on worksheet 3.



**Table 7-4** Classification of vegetation cover as to degree of retardance

Retardance	Cover	Condition
A	Weeping lovegrass	Excellent stand, tall (average 30 in)
	Reed canarygrass or Yellow bluestem ischaemum	Excellent stand, tall (average 36 in)
B	Smooth bromegrass	Good stand, mowed (average 12 to 15 in)
	Bermudagrass	Good stand, tall (average 12 in)
	Native grass mixture (little bluestem, blue grama, and other long and short midwest grasses)	Good stand, unmowed
	Tall fescue	Good stand, unmowed (average 18 in)
	Sericea lespedeza	Good stand, not woody, tall (average 19 in)
	Grass-legume mixture—Timothy, smooth bromegrass, or orchardgrass	Good stand, uncut (average 20 in)
	Reed canarygrass	Good stand, uncut (average 12 to 15 in)
	Tall fescue, with birdsfoot trefoil or ladino clover Blue grama	Good stand, uncut (average 18 in) Good stand, uncut (average 13 in)
C	Bahiagrass	Good stand, uncut (6 to 8 in)
	Bermudagrass	Good stand, mowed (average 6 in)
	Redtop	Good stand, headed (15 to 20 in)
	Grass-legume mixture—summer (orchardgrass, redtop, Italian ryegrass, and common lespedeza)	Good stand, uncut (6 to 8 in)
	Centipedegrass	Very dense cover (average 6 in)
	Kentucky bluegrass	Good stand, headed (6 to 12 in)
D	Bermudagrass	Good stand, cut to 2.5-in height
	Red fescue	Good stand, headed (12 to 18 in)
	Buffalograss	Good stand, uncut (3 to 6 in)
	Grass-legume mixture—fall, spring (orchardgrass, redtop, Italian ryegrass, and common lespedeza)	Good stand, uncut (4 to 5 in)
	Sericea lespedeza or Kentucky bluegrass	Good stand, cut to 2-in height. Very good stand before cutting
E	Bermudagrass	Good stand, cut to 1.5-in height
	Bermudagrass	Burned stubble

**Table 7-5** Retardance curve index by retardance class

SCS retardance class	Retardance curve index $C_I$
A	10.0
B	7.64
C	5.60
D	4.44
E	2.88

Interim Runoff Calculations  
A.B. Brown Landfill - Cell 17 North

SCS Run-Off Equation

$$Q = \frac{(P - I_a)^2}{(P - I_a) + S}$$

where

- Q = runoff (in)
- P = rainfall (in)
- S = potential maximum retention after runoff begins (in) and
- I<sub>a</sub> = initial abstraction (in)

$$S = \frac{1000}{CN} - 10$$

$$S = 1000/79 - 10 = 2.658$$

$$Q = \frac{(5.4 - 0.2 * 2.658)^2}{5.4 + 0.8 * 2.658} \approx 3.15 \text{ in.}$$

[Amount of Runoff]

SCS Runoff Volume

Total Storm Volume  
= (3.15 in./12in.) \* (3.10 acres) = 0.81 ac-ft

SCS Watershed Variables Defined

CN = Curve Number = 79

P = Rainfall = 5.4 in. (25-Year, 24-Hour Storm)

A (Area of Watershed, Typical Interim Cell)  
A = 3.10 acres

Interim Runoff Calculations  
A.B. Brown Landfill - Cell 17 South

SCS Run-Off Equation

$$Q = \frac{(P - I_a)^2}{(P - I_a) + S}$$

where

- Q = runoff (in)
- P = rainfall (in)
- S = potential maximum retention after runoff begins (in) and
- I<sub>a</sub> = initial abstraction (in)

$$S = \frac{1000}{CN} - 10$$

$$S = 1000/79 - 10 = 2.658$$

$$Q = \frac{(5.4 - 0.2 * 2.658)^2}{5.4 + 0.8 * 2.658} \approx 3.15 \text{ in.}$$

[Amount of Runoff]

SCS Runoff Volume

Total Storm Volume  
= (3.15 in./12in.) \* (2.67 acres) = 0.70 ac-ft

SCS Watershed Variables Defined

CN = Curve Number = 79

P = Rainfall = 5.4 in. (25-Year, 24-Hour Storm)

A (Area of Watershed, Typical Interim Cell)  
A = 2.67 acres

Interim Runoff Calculations  
A.B. Brown Landfill - Cell 18 North

SCS Run-Off Equation

$$Q = \frac{(P - I_a)^2}{(P - I_a) + S}$$

where

- Q = runoff (in)
- P = rainfall (in)
- S = potential maximum retention after runoff begins (in) and
- I<sub>a</sub> = initial abstraction (in)

$$S = \frac{1000}{CN} - 10$$

$$S = 1000/79 - 10 = 2.658$$

$$Q = \frac{(5.4 - 0.2 * 2.658)^2}{5.4 + 0.8 * 2.658} \approx 3.15 \text{ in.}$$

[Amount of Runoff]

SCS Runoff Volume

Total Storm Volume  
= (3.15 in./12in.) \* (3.97 acres) = 1.04 ac-ft

SCS Watershed Variables Defined

CN = Curve Number = 79

P = Rainfall = 5.4 in. (25-Year, 24-Hour Storm)

A (Area of Watershed, Typical Interim Cell)  
A = 3.97 acres

Interim Runoff Calculations  
A.B. Brown Landfill - Cell 18 South

SCS Run-Off Equation

$$Q = \frac{(P - I_a)^2}{(P - I_a) + S}$$

where

- Q = runoff (in)
- P = rainfall (in)
- S = potential maximum retention after runoff begins (in) and
- I<sub>a</sub> = initial abstraction (in)

$$S = \frac{1000}{CN} - 10$$

$$S = 1000/79 - 10 = 2.658$$

$$Q = \frac{(5.4 - 0.2 * 2.658)^2}{5.4 + 0.8 * 2.658} \approx 3.15 \text{ in.}$$

[Amount of Runoff]

SCS Runoff Volume

Total Storm Volume  
= (3.15 in./12in.) \* (4.28 acres) = 1.12 ac-ft

SCS Watershed Variables Defined


CN = Curve Number = 79

P = Rainfall = 5.4 in. (25-Year, 24-Hour Storm)

A (Area of Watershed, Typical Interim Cell)  
A = 4.28 acres

Reference 4: NOAA Technical Paper No. 40

# RAINFALL - 25 YEAR FREQUENCY - 24 HOUR DURATION



REFERENCE  
TECHNICAL PAPER NO. 40  
NATIONAL WEATHER SERVICE



STATE OF INDIANA  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF WATER






## Appendix D: Surface Water Control and Design Plan Sheets

<b>SHEET NO.</b>	<b>DESCRIPTION</b>
*1	Site Plan
*2	Final Cover Grades - Surface Water Control Plan
*3	Details – Terrace Berm and Perimeter Ditch

\*Plan sheets from previously approved Indiana Department of Environmental Management (IDEM) Restricted Waste Type III Landfill 2007 and 2012 minor modification applications





Project Number: 170101149  
 Drawing File: [unclear]  
 Site File Location: [unclear]  
 Date: 9/2021  
 Scale: AS SHOWN  
 App'd By: [unclear] Drawn By: [unclear]

ATC GROUP SERVICES, LLC  
 7988 CENTERPOINT DR.  
 SUITE 100  
 INDIANAPOLIS, IN 46256  
 PHONE +1 317 849 4900  
 FAX +1 317 849 4278  
 WWW.ATCGROUPSERVICES.COM

**ATC**

Drawing Title:  
**SITE PLAN**  
**TYPE III RWS LANDFILL**  
**85TH WELBORN ROAD**  
**MOUNT VERNON, INDIANA 47620**

Sheet:  
**1**  
 of 1 sheets



- LEGEND:**
- PERMITTED SOLID WASTE BOUNDARY
  - EXISTING TOPOGRAPHIC ELEVATIONS
  - 4.30 PERMITTED FINAL GRADES
  - 4.30 PROPOSED MINOR MOD FINAL GRADE REVISION
  - APPROXIMATE LOCATION OF DOWNDRAIN OR CULVERT OUTLET RIPRAP
  - APPROXIMATE LOCATION OF TERRACE DIVERSION
  - FINAL COVER DIVERSION BERMS
  - DOWNDRAIN INLET WITH RIPRAP SPLASH PAD
  - TOE DRAIN
  - TOE DRAIN OUTLET AT LOW POINTS OF TOE DRAINS
  - APPROXIMATE LOCATION OF SLURRY WALL
  - APPROXIMATE LOCATION OF GRADIENT CONTROL TRENCH
  - PERMANENT EROSION CONTROL MAT OR APPROVED ALTERNATIVE.

PREVIOUSLY SUBMITTED 60 IN. DIA. CULVERT WITH UPSTREAM DROP INLET OF 18 IN. DIA. TOP OF DROP INLET AT EL. 401, UPSTREAM INVERT OF CULVERT AT EL. 398 AND CULVERT SLOPE AT 0.1%.

PREVIOUSLY SUBMITTED 18 IN. DIA. CULVERT WITH UPSTREAM INVERT AT EL. 370 AND A 2.3% SLOPE.

Project Number:	170LF01149
Drawing File:	SEE LEFT
Date:	9/2021
Scale:	AS SHOWN
App'd By:	JC
Chk By:	DB
Drn. By:	DB

Company Name:  
**SOUTHERN INDIANA GAS AND ELECTRIC COMPANY**  
 A.B. BROWN GENERATING STATION  
 TYPE III RESTRICTED WASTE LANDFILL  
 WWW.ATCGROUPSERVICES.COM



Drawing Title:  
**PROPOSED FINAL COVER GRADES  
 TYPE III RESTRICTED WASTE LANDFILL  
 A.B. BROWN GENERATING STATION**

THREE-I ENGINEERING, INC.  
 A.B. BROWN UPDATE  
 PREPARED BY: GLE. MC. NEWBORN, INDIANA  
 DATE OF PHOTOGRAPHY: 2-18-2016  
 CS - 2'

